

<b>NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK &amp; GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS</b>						
<b>SCHEDULE-C PRIVATE WARD</b>						
<b>Sl.No</b>	<b>Quantity</b>		<b>Description of the work</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1			Supply and laying of open wiring for light / calling bell / exhaust fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc. including supply and fixing of 3 terminal ceiling rose / holder controlled by 6Amps one-way switch in existing metal box.			
a	9.00	Pts	3.0 mts point		1Pt	
b	15.00	Pts	4.5 mts point		1Pt	
c	24.00	Pts	6.0 mts point		1Pt	
2			Supply and laying of open wiring for ceiling fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc. including supply and fixing of 3 terminal ceiling rose / holder controlled by 6Amps one-way switch and regulated by socket type regulator in existing metal box.			
a	2.00	Pts	4.5 mts point		1Pt	
b	9.00	Pts	6.0 mts point		1Pt	
3	180.00	Mtrs	Supply and laying of wiring for the point wiring using 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc.		1Mtr	
4	6.00	Nos	Installation of 12 " Exhaust fan (Ex. Fan will be supplied by CMC)		1No	
5	26.00	Nos	Installation of 36W 4 Feet LED batten light (Light fitting will be supplied by CMC)		1No	
6	16.00	Nos	Installation of 18W LED recess mounted round downlighter (Light fitting will be supplied by CMC)		1No	
7	6.00	Nos	Installation of Foot lamp (Light fitting will be supplied by CMC)		1No	
8	11.00	Nos	Installation of 1200mm Sweep ceiling fan (Ceiling fan will be supplied by CMC)		1No	
9	1.00	No	Supply and fixing of 12 x 8 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
10	4.00	Nos	Supply and fixing of 8 x 6 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
11	8.00	Nos	Supply and fixing of 6 x 4 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
12	4.00	Nos	Supply and fixing of 4 x 4 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
13	2.00	Nos	Supply and fixing of 3 x 6A (3nos Switch & 3nos Socket) in 8 x 6 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc.,(Open)		1No	

<b>NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK &amp; GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS</b>						
<b>SCHEDULE-C PRIVATE WARD</b>						
<b>Sl.No</b>	<b>Quantity</b>		<b>Description of the work</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
14	16.00	Nos	Supply and fixing of 2 x 6A (2nos Switch & 2nos Socket) in 6 x 4 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc.,(Open)		1No	
15	7.00	Nos	Supply and fixing of 1 x 20A (1noSwitch & 1no Socket) in 6 x 4 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc., (Open)		1No	
17	330.00	Mtrs	Open wiring for run of main using 2x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire and 1x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire for earth in 19 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc.n)		1Mtr	
18	60.00	Mtrs	Open wiring for run of main using 4x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire and 2x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire for earth in 25 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc..		1Mtr	
19	90.00	Mtrs	Open wiring for run of main using 2x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire and 1x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire for earth in 19 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc.,,		1Mtr	
20	50.00	RM	Supply and laying of 1RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Open)		1RM	
21	30.00	RM	Supply and laying of 2RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Open)		1RM	
22	60.00	RM	Supply and laying of 1RxTelephone cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Open)		1RM	
23	1.00	No	Supply, erection, testing and commissioning of 12way Single phase MCB DB including supply and fixing of 10nos 6/10/16/20 Amp SP MCB's and 1no 40A DP 300mA RCCB as incomer.(UPSDB)		1No	
24	1.00	No	Supply, erection, testing and commissioning of 12way Single phase MCB DB including supply and fixing of 10nos 6/10/16/20 Amp SP MCB's and 1no 40A DP 30mA RCCB as incomer.(LDB)		1No	
25	110.00	Mtrs	Supply, laying, testing and commissioning of 3C 16 sq.mm XLPE insulated armoured Aluminium LT cable including supply and fixing of clamps, nuts and bolts, screws, identification tags, ferrules etc., required for clamping intervals as necessary.		1Mtr	
26	4.00	Sets	Supply of all materials and termination of the 3C 16 sq.mm XLPE insulated armoured aluminium LT.Cables using flange type brass cable glands (including gland earthing, Cable end lugs,cable tags)		1Set	
			<b>Sub Total</b>			
			<b>Sub-total Amount -Excl.GST-18%-C/O Consoildated Summary</b>			