

NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK & GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS						
SCHEDULE-D GENERAL WARD						
Sl.No	Quantity		Description of the work	Rate	Unit	Amount
1			Supply and laying of open wiring for light / calling bell / exhaust fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc. including supply and fixing of 3 terminal ceiling rose / holder controlled by 6Amps one-way switch in existing metal box.			
a	18.00	Pts	3.0 mts point		1Pt	
b	2.00	Pts	4.5 mts point		1Pt	
c	15.00	Pts	6.0 mts point		1Pt	
2			Supply and laying of open wiring for ceiling fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc. including supply and fixing of 3 terminal ceiling rose / holder controlled by 6Amps one-way switch and regulated by socket type regulator in existing metal box.			
a	1.00	Pt	4.5 mts point		1Pt	
b	17.00	Pts	6.0 mts point		1Pt	
3	120.00	Mtrs	Supply and laying of wiring for the point wiring using 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bend, nails, etc.		1Mtr	
4	4.00	Nos	Installation of 12 " Exhaust fan (Ex. Fan will be supplied by CMC)		1No	
5	19.00	Nos	Installation of 36W 4 Feet LED batten light (Light fitting will be supplied by CMC)		1No	
7	12.00	Nos	Installation of 18W LED recess mounted round downlighter (Light fitting will be supplied by CMC)		1No	
9	18.00	Nos	Installation of 1200mm Sweep ceiling fan (Ceiling fan will be supplied by CMC)		1No	
11	2.00	Nos	Supply and fixing of 8 x 6 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
12	1.00	Nos	Supply and fixing of 6 x 4 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
13	17.00	Nos	Supply and fixing of 4 x 4 x 2 MS box along with 2mm Hylam sheet necessary accessories etc., (Open)		1No	
14	2.00	Nos	Supply and fixing of 3 x 6A (3nos Switch & 3nos Socket) in 8 x 6 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc..(Open)		1No	
15	18.00	Nos	Supply and fixing of 2 x 6A (2nos Switch & 2nos Socket) in 6 x 4 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc..(Open)		1No	
16	2.00	Nos	Supply and fixing of 1 x 6A (1no Switch & 1no Socket) in 4 x 4 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc..(Open)		1No	
17	12.00	Nos	Supply and fixing of 1 x 20A (1no Switch & 1no Socket) in 6 x 4 x 2 MS box along with 2mm thick Hylam sheet necessary accessories etc.. (Open)		1No	

NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK & GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS						
SCHEDULE-D GENERAL WARD						
Sl.No	Quantity		Description of the work	Rate	Unit	Amount
19	300.00	Mtrs	Open wiring for run of main using 2x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire and 1x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire for earth in 19 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc n)		1Mtr	
20	90.00	Mtrs	Open wiring for run of main using 4x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire and 2x36/.3mm (2.5sq.mm.) PVC insulated unsheathed copper wire for earth in 25 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc		1Mtr	
21	225.00	Mtrs	Open wiring for run of main using 2x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire and 1x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire for earth in 19 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc		1Mtr	
22	40.00	Mtrs	Open wiring for run of main using 4x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire and 2x56/.3mm (4sq.mm.) PVC insulated unsheathed copper wire for earth in 25 mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like PVC bends, nails etc		1Mtr	
23	30.00	Mtrs	Supply and laying of 1RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Open)		1Mtr	
24	70.00	Mtrs	Supply and laying of 2RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Open)		1Mtr	
			Sub Total			
			Sub-total Amount -Excl.GST-18%-C/O Consoildated Summary			