

NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK & GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS						
SCHEDULE-E PRIVATE WARD						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
			Hose reel system			
1			Supply, laying, testing and commissioning of 'C' class M.S pipe - heavy IS1239 of following dia with necessary fittings, specials welded joints and flanged joints near valves and other important places including necessary support(as given in the technical specification) and painting with one coat of zinc chromate primer and 2 or more coats synthetic enamel paint to make good finish etc complete			
a			25 mm dia			
i	12	mts	Supply		1 RM	
ii	12	mts	Laying, testing, commissioning		1 RM	
b			100 mm dia			
i	2	mts	Supply		1 RM	
ii	2	mts	Laying, testing, commissioning		1 RM	
2			Labour charges for removing following dia MS pipe and handing over the same to the Engineer incharge as directed etc complete			
a	3	mts	25mm dia		1 RM	
b	2	mts	50mm dia		1 RM	
c	2	mts	100mm dia		1 RM	
3	1	No	Labour charges for removing Hosereel drum with necessary accessories without damage from the existing location and fixing the same near emergency exit etc complete		1 No	
			Fire Alarm System			
4	90	mts	Supply and laying 2 core 1.5 sqmm copper Armoured cable with necessary accessories etc complete		1 RM	
5	2	Nos	Supply, installation, testing and commissioning of Conventional type System sensor / Apollo make smoke detectors in MS Box with necessary accessories etc complete (MS box will be paid separately)		1 No	
6	1	Nos	Supply and installation, testing of conventional type hooter (Agni make)		1 No	
			Sub total			
			Sub-total Amount -Excl.GST-18%-C/O Consoildated Summary			