

| NAME OF WORK: CONVERSION OF DUTY DOCTOR'S ROOMS TO PRIVATE BLOCK & GENERAL WARD AT CMC VELLORE CHITTOOR CAMPUS | | | | | | |
|--|----------|-----|---|------|------|--------|
| | | | SCHEDULE-F GENERAL WARD | | | |
| Sl.No | Quantity | | Description of the work | Rate | Unit | Amount |
| | | | Hose reel system | | | |
| 1 | | | Supply, laying, testing and commissioning of 'C' class M.S pipe - heavy IS1239 of following dia with necessary fittings, specials welded joints and flanged joints near valves and other important places including necessary support(as given in the technical specification) and painting with one coat of zinc chromate primer and 2 or more coats synthetic enamel paint to make good finish etc complete | | | |
| a | | | 25 mm dia | | | |
| i | 10 | mts | Supply | | 1 RM | |
| ii | 10 | mts | Laying, testing, commissioning | | 1 RM | |
| b | | | 100 mm dia | | | |
| i | 2 | mts | Supply | | 1 RM | |
| ii | 2 | mts | Laying, testing, commissioning | | 1 RM | |
| 2 | 1 | No | Labour charges for removing Hosereel drum with necessary accessories without damage from the existing location and fixing the same near emergency exit etc complete | | 1 No | |
| | | | Fire Alarm System | | | |
| 3 | 360 | mts | Supply and laying 2 core 1.5 sqmm copper Armoured cable with necessary accessories etc complete | | 1 RM | |
| 4 | 11 | Nos | Supply, installation, testing and commissioning of Conventional type System sensor / Apollo make smoke detectors in MS Box with necessary accessories etc complete (MS box will be paid separately) | | 1 No | |
| 5 | 2 | Nos | Supply, installation, testing and commissioning of Conventional type System sensor / Apollo make Multi sensor detectors in MS Box with necessary accessories etc complete (MS box will be paid separately) | | 1 No | |
| 6 | 1 | Nos | Supply and installation, testing of conventional type MCP - break glass type (Agni Make) | | 1 No | |
| 7 | 1 | Nos | Supply and installation, testing of conventional type hooter (Agni make) | | 1 No | |
| | | | Sub total | | | |
| | | | Sub-total Amount -Excl.GST-18%-C/O Consoildated Summary | | | |