

NAME OF THE WORK: PROVIDING TROLLEY PARKING BAY FOR MAIN OR TROLLEYS NEAR O1 WEST @ FIRST FLOOR OF CMC, TOWN CAMPUS.						
			TENDER SCHEDULE-A			
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
1	1.00	M ³	Demolishing brick walls in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
2	10.00	RM	Labour charges for removing the existing GI/PVC pipes upto 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1RM	
3	10.00	RM	Labour charges for removing the existing GI/PVC pipes above 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1RM	
4	15.00	M ²	Labour charges for removing existing MS Grill completely and the same to be handed over to disposal including clearing the debris away from site as directed.		1M ²	
5	10.00	Kgs	Supplying fabricating,placing and tying in position of steel reinforcement including cost of 18 gauge MS binding wire etc.complete .		1Kg	
6	0.50	M ³	Brick wall in Cement-mortar 1:6,230mm thick using country bricks of size 230x100x70mm (Kiln burnt)including cost all materials and curing etc., complete. (super structure up to floor v level)		1M ³	
7	6.00	M ²	Brick work in CM 1:4 for partition wall using country bricks of size 230x100x70mm(Kiln burnt) including cost of all materials, labour for placing 2nos - 6mm dia MS rods at every 3rd course and curing etc. complete (steel will be measured separately & Supplied by Dept free of cost.).		1M ²	
8	15.00	M ²	Plastering with CM 1:5, 12mm thick over new surface of internal Brick walls including cost of all materials and curing etc. complete.		1M ²	
9	65.00	M ²	Grano floor finishing with CC 1:1.50:3 using M-sand and 3mm to 8mm size HBG machine broken chips including cost of all materials, laying, consolidation, thread lining if necessary, neat finishing and curing etc. complete. 40mm average thick.		1M ²	
10	145.00	Kgs	Supplying and fixing in position of MS Grill door and MS Grill Over Brick wall incl. cost of all materials, fabrication charges, 1 coat of zinc chromate anti-corrosive primer etc. Complete as per sketch and specifications		1Kg	
11	37.00	M ²	Supplying and fixing in position of Aluminium partition of required sizes incl. cost of all materials ,required furniture fittings etc complete as per Sketch and Specification		1M ²	
12	30.00	Kgs	Supplying and fixing of required size brackets and clamps using MS Angles, MS flats, and MS threaded rods as instructed by Engineer including one coat zinc chromate primer, two coats with synthetic enamel paint making holes in wall for fixing cement concrete for packing finishing the surfaces etc., complete		1Kg	
13			Supplying and fixing of the following diaSupreme make SWR PVC Type-A pipes including cutting charges,cost of cement solvent for joining and fixing with necessary SWR PVC plumbing specials for rain water line including necessary scaffolding etc., complete but including cost of specials and MS brackets which will be paid seperately.			
a	10.00	M	110 mm dia		1RM	
b	10.00	M	160 mm dia		1RM	

NAME OF THE WORK: PROVIDING TROLLEY PARKING BAY FOR MAIN OR TROLLEYS NEAR O1 WEST @ FIRST FLOOR OF CMC, TOWN CAMPUS.					
			TENDER SCHEDULE-A		
Sl.No.	Quantity		Description of the work	Rate	Unit Amount
14			Supplying of G.I special clamp with coach screw, U bolt , nut & washer of the following sizes of G.I Pipe supports and specifications etc. complete.		
a	2.00	No	100 mm length		1No
b	2.00	No	230 mm length		1No
15	60.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over new/old walls and ceilings with one coat of water based primer after preparation of the surface smooth and even with Birla wall care putty/ approved equivalent including cost of all materials, proper roller finish, brush etc. complete.		1M ²
16	10.00	M ²	Painting two coats using synthetic enamel paint of approved make & colour over the old / new ironwork incl. surface preparation, necessary putty, cost of all materials, brush and scaffolding etc. Complete. (to be specially authorized in writing)		1M ²
17	30.00	M ²	Scraping completely and cleaning the white (or) colour washed surface (or) snowcem surface of old walls and ceilings using putty plate, sand paper and wire brush etc. incl. scaffolding and clearing the debris away from site etc. complete. (For Interior and Exterior surfaces).		1M ²
18	1.00	Lorry loads	Transporting the debris by lorry from CMC Town Campus to outside of the campus including loading and unloading charges etc. complete.(Capacity 5.50 M ³ per lorry load).		1 Lorry
				Sub Total	
			Excl.GST-18% -C/O to Consolidated Abstract		