

NAME OF THE WORK: CONSTRUCTION OF SIMULATION LAB ON THE FIRST FLOOR OF COLLEGE OF NURSING ACADEMIC BLOCK AT CMC VELLORE, CHITTOOR CAMPUS						
SCHEDULE-A-Civil works			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
1	160.00	M ²	Supplying, making & fixing in position of 84mm thick Drywall partition (Overall thickness) up to ceiling height in all floors using 10mm thick Calcium silicate board for both sides of panels, 63.50x38.10x1.95mm Aluminium Box section for forming 600x850mm grid framing for supporting the panel boards, including cost of necessary tools & materials, screws and nails, filling the partition joints with silicone sealant, etc. Complete, as per sketch and specification.		1M ²	
2	250.00	M ²	Supply and fixing " DAIKEN " gypsum ceiling tiles 9.5mm thick laminated with aluminium foil on one side and pvc sheet on the other side with hot dipped galvanized steel grid work surface chemically cleaned capping PVC finished in backed polyester paint, main tees of size 33(H) x 24mm every 1.20m center to center stitched cross tea at 0.60m center to center to form a grid of size (600 x 600mm & suspending the grid from roof using 3mm GI rod, 6mm nylon rawl plug & I bolt at every 1200 intervals laying "DAIKEN" gypsum 155 ceiling tiles of size 600 x600mm over the formed grid having fire rating of 60 minutes as per BS 479/23 of 1987, light reflection of 85% over the formed Grid.		1M ²	
3			Supplying and fixing in position of following types of Wooden Doors frame with single/double shutters including furniture fittings as per sketch and specification.			
a	8.00	M ²	Door-D-1200x2100MM		1M ²	
b	7.00	M ²	Door-D1-1050x2100MM		1M ²	
4	20.00	M ²	Supplying and fixing in position of Fixed (one way) Glazing with frame including cost of all materials, furniture fittings etc complete as per Sketch and Specifications (Size of FG4-2400x1200mm)		1M ²	
5			Supplying and fixing in position of Fixed Double Glazing with frame including cost of all materials, furniture fittings etc complete as per Sketch and Specifications			
a	42.60	M ²	Size:3200/3500/3600X1450/1850MM		1M ²	
b	7.40	M ²	Size:1000X1850MM		1M ²	
6	6.00	M ²	Supply and fixing work table with Drawer cost of all materials, furniture fittings etc complete as per Sketch and Specifications (Size of 3300x600x900mm)		1M ²	
7	1.20	M ²	Supply and fixing Shoe rack cost of all materials, furniture fittings etc complete as per Sketch and Specifications (Size of 600x300x450mm)		1M ²	
8	10.00	M ²	Painting one coat using Acrylic emulsion paint of appd. Make & colour over old painted surfaces of walls & ceilings incl. surface preparation with necessary putty, Brush, cost of all materials & scaffolding etc. Complete.		1M ²	

NAME OF THE WORK: CONSTRUCTION OF SIMULATION LAB ON THE FIRST FLOOR OF COLLEGE OF NURSING ACADEMIC BLOCK AT CMC VELLORE, CHITTOOR CAMPUS						
SCHEDULE-A-Civil works			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
9	500.00	M ²	Painting two coats using Acrylic emulsion paint of appd. Make & Colour over old painted surfaces of walls & ceilings incl.surface preparation , necessary putty , brush, cost of all materials & scaffolding etc. Complete.		1M ²	

NAME OF THE WORK: CONSTRUCTION OF SIMULATION LAB ON THE FIRST FLOOR OF COLLEGE OF NURSING ACADEMIC BLOCK AT CMC VELLORE, CHITTOOR CAMPUS						
SCHEDULE-A-Civil works			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
10	500.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over walls with one coat of water based primer after preparation of the surface smooth and even with Birla wall care putty / approved equivalent including cost of all materials, proper roller finish, brush and scaffolding etc. complete.		1M ²	
11	10.00	M ²	Painting one coat using synthetic enamel paint of approved make & color over the old woodwork including painting the furniture fittings where required surface preparation with application of putty, cost of all materials, brush & scaffolding etc. Complete.		1M ²	
12	20.00	M ²	Painting two coats using synthetic enamel of approved make & colour over the old woodwork incl. painting the furniture fittings where required, surface preparation with application of putty, cost of all materials, brush and scaffolding etc. complete.		1M ²	
13	20.00	M ²	Painting two coats with synthetic enamel paint of approved make and colour over new wood works with one coat of wood primer incl, painting the furniture fittings where required, surface preparation with application of putty, cost of all materials brush and scaffolding etc Complete.		1M ²	
14	10.00	M ²	Painting one coat using synthetic enamel of approved make & colour over the old ironwork incl. surface preparation, necessary putty, cost of all materials, brush and scaffolding etc Complete.		1M ²	
15	20.00	M ²	Painting two coats with synthetic enamel paint of approved make & colour over the old ironwork including surface preparation, necessary putty, cost of all materials, brush and scaffolding etc. complete		1M ²	
16	6.00	Nos	Supplying and fixing in position of Hydraulic door closer (Rolex Make) to wooden/aluminium doors complete set including required screws and nails etc., complete.		1No	
17	3.00	M ³	Plain cement concrete 1:2:4 using 20mm size HBG machine broken jelly, M- sand including cost of all materials, mixing in mixer machine, laying, consolidation, self finishing and curing etc. complete for bed blocks.		1M ³	
18	12.00	M ²	Supplying, fixing and removing of 12mm thick plywood Centering and Shuttering to correct line and levels fully leak proof to avoid leakage of cement slurry including strutting etc., Complete. Foundation upto plinth level.		1M ²	
19	6.00	Nos	Making through holes in Plain or Reinforced Cement Concrete/Brickwork with Diamond Core Drilling System by using BOSCH power tools of diameter - Depth per cm upto 200mm (Plain or Reinforced Cement Concrete).		1No	
			Sub Total			
(Excl. GST) C/o to CONSOLIDATED SUMMARY						