

NAME OF THE WORK: RENOVATION OF BANKING, BILLING, CASH SECTION, COST ACCOUNTS AND PROVIDENT FUND SECTION IN ACCOUNTS DEPARTMENT, FIRST FLOOR OF ADMINISTRATIVE BLOCK @ CMC, TOWN CAMPUS.						
TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
1	3.00	M ³	Demolishing brick walls in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
2	1.00	M ³	Demolishing brick walls in Lime mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
3	21.00	Nos	Labour charges for removing the existing wooden cupboards & pelmets (frame with shutters) complete set without any damage including all available fittings and the same to be handed over to deptl.store as directed.		1No	
4	25.00	RM	Labour charges for removing the existing GI/PVC pipes upto 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1RM	
5	15.00	RM	Labour charges for removing the existing GI/PVC pipes above 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1RM	
6	3.00	Nos	Labour charges for removing the 15mm dia to 25mm dia existing wheel valve/Gate valve/ open stop cock etc. with all available specials without any damage and the same to be handed over to deptl.store as directed.		1No	
7	2.00	M ²	Labour charges for dismantling precast concrete including clearing the debris away from site as directed.		1M ²	
8	4.00	Nos	Labour charges for removing the existing wash hand basin/sink with all available fittings complete set without any damage and the same to be handed over to deptl.store as directed.		1No	
9	8.00	Nos	Labour charges for removing the existing towel rod & mirrors or any other usable accessories without any damage and the same to be handed over to deptl.store as directed.		1No	
10	4.00	Nos	Labour charges for removing the existing brass/CP tap without any damage and the same to be handed over to deptl.store as directed.		1No	
11	25.00	M ²	Labour charges for chipping and removing the existing cement/lime plastering from wall surface and wherever necessary and clearing the debris away from site as directed.		1M ²	
12	1.00	M ³	Labour charges for Chipping / removing the existing grano flooring without affecting the adjacent area including clearing the debris away from site as directed.		1M ³	
13	15.00	M ²	Labour charges for dismantling wooden boardings in lining of walls, Working Table top,,etc., and the same to be handed over to deptl.store as directed.		1M ²	
14	85.00	Kgs	Supplying fabricating,placing and tying in position of steel reinforcement including cost of 18 gauge MS binding wire etc.complete for all RCC works		1Kg	
15	0.50	M ³	Casting and fixing in position of RCC 1:2:4 for precast slabs using 3 to 8mm size HBG machine broken chips, coarse sand including cost of all materials, necessary mould and platform, smooth finishing with CM 1:3 for all exposed surfaces and curing etc. complete but excluding cost of steel and fabrication.		1M ³	

NAME OF THE WORK: RENOVATION OF BANKING, BILLING, CASH SECTION, COST ACCOUNTS AND PROVIDENT FUND SECTION IN ACCOUNTS DEPARTMENT, FIRST FLOOR OF ADMINISTRATIVE BLOCK @ CMC, TOWN CAMPUS.						
TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
16	4.00	M ³	Brick wall in Cement-mortar 1:6,230mm and above thick using country bricks of size 230x100x70mm (Kiln burnt)including cost all materials and curing etc., complete.super structure up to floor v level		1M ³	
17	3.00	M ²	Brick work in CM 1:4 for partition wall using country bricks of size 230x100x70mm(Kiln burnt) including cost of all materials, labour for placing 2nos - 6mm dia MS rods at every 3rd course and curing etc. complete (steel will be measured separately & Supplied by Dept free of cost.).		1M ²	
18	5.00	M ²	Brick on edge work in CM 1:4 using country bricks of size 230x100x70mm (kiln burnt) including cost of all materials and curing etc. complete for cupboard,open shelves,working platform support walls.		1M ²	
19	20.00	M ²	Plastering with CM 1:5, 12mm thick over new surface of internal Brick walls including cost of all materials and curing etc. complete.		1M ²	
20	2.50	M ²	Plastering with CM 1:3, 12mm thick for all RCC exposed surfaces to ceiling roof projections incl. cost of all materials,hacking, neat finishing and curing etc. complete in all floors.		1M ²	
21	60.00	M ²	Base Plastering with CM 1:5, 20mm thick over chipped surface of existing brick walls including cost of all materials and curing etc. complete in all floors.		1M ²	
22	20.00	M ²	Grano floor finishing with CC 1:1.50:3 using sand and 3mm to 8mm size HBG machine broken chips including cost of all materials, laying, consolidation, thread lining if necessary, neat finishing and curing etc. complete. 40mm average thick.		1M ²	
23	6.00	M ²	Supplying and fixing of Glazed Plain wall tiles 1st quality 300x450mm/300x600mm size of approved make and colour set in CM 1:3 base including pointing with white cement mixed with colour pigments, providing best quality PVC corner edge beads, cleaning and curing etc. complete for dadoing. (Basic cost of tiles :- Rs.450.00/1M²- Excl.GST)		1M ²	
24	2.00	M ²	Supplying and fixing in position of highly polished Granite slab 18 to 20mm thick of approved quality and approved sample, set in CM 1:3, including cost of all materials, pointing white cement with matching colour pigments, cleaning and curing etc. complete. (Basic rate of granite Rs. 2,500.00 /1M²- Excl.GST). For Table top, Floor strips		1M ²	
25	2.00	Nos	Extra for providing opening of required size & shape for wash basins/ sink in platform and similar location in marble/Granite/stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete.		1No	
26	3.00	RM	Providing full nosing to exposed edges of granite in table top etc.complete		1M	
27			Supplying and fixing in position of following sizes of Wooden window frame with shutter complete set including cost of all materials and furniture fittings as per sketch and specification.			
a	1.26	M ²	Window -W1-1050x1200		1M ²	
b	1.32	M ²	Window -W2-1100x1200		1M ²	
c	1.32	M ²	Window -W2a-1100x1200 (Without Grill)		1M ²	

NAME OF THE WORK: RENOVATION OF BANKING, BILLING, CASH SECTION, COST ACCOUNTS AND PROVIDENT FUND SECTION IN ACCOUNTS DEPARTMENT, FIRST FLOOR OF ADMINISTRATIVE BLOCK @ CMC, TOWN CAMPUS.

TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
d	4.32	M ²	Window -W5a-1200x1800 (Mesh Shutter only)		1M ²	
28	-		Supplying and fixing in position of Underneath Cup boards frame with openable shutters including cost of all materials ,required furniture fittings etc.,, complete as per sketch and specifications.			
a	0.75	M ²	Cupboard -UCB(Size-840x830MM)@ Hand Wash Room			
b	2.00	M ²	Cupboard -UCB(Size-1450x830MM)@ Hand Wash Room			
29	12.00	M ²	Supplying and fixing in position of covering/closing the openings and ventilators wherever necessary using 12mm thick BWP approved make plywood with the existing frame including cost of all materials,necessary screws, nails,fixing and finishing in all respects etc.,, complete.		1M ²	
30	48.00	Kgs	Supplying and fixing in position of MS grill with outer frame ,approved design using Ms flats,square rods including cost of all materials,fabrication charges,1 coat of Zinc chromate primer and two coat of synthetic enamel paint etc etc.,, complete		1Kg	
31	-		Supplying and fixing of the following PVC pipes including cutting charges, cost of cement solvent for joining and fixing with necessary specials,cost of all materials etc.,, complete for internal pipe lines. (ABOVE GROUND LEVEL)			
a	15.00	RM	40mm dia 6Kgs/CM ² (incl. specials)		1RM	
b	11.00	RM	50mm dia 6Kgs/CM ² (incl. specials)		1RM	
c	6.00	RM	63mm dia 4Kgs/CM ² (incl. specials)		1RM	
32	-		Supplying of G.I special clamp with coach screw, U bolt , nut & washer of the following sizes of G.I Pipe supports and specifications etc. complete.			
a	9.00	Nos	100 mm length		1No	
b	9.00	Nos	230 mm length		1No	
33	-		Supplying , cutting,threading, laying and joining of G.I. pipes ' B ' class ISI make with necessary ' UNIK' make specials including cost of all required materials, clamps, teak wood plugs and screws etc.,, complete. (ABOVE GROUND LEVEL)			
a	22.00	RM	15mm dia		1RM	
b	15.00	RM	20mm dia		1RM	
c	11.00	RM	25mm dia		1RM	
d	11.00	RM	32mm dia		1RM	
34	2.00	Nos	Supplying and fixing in position of Porcelain sink 600x450x250mm size including cost of all fittings such as ,CP waste coupling etc.,, complete.		1No	

NAME OF THE WORK: RENOVATION OF BANKING, BILLING, CASH SECTION, COST ACCOUNTS AND PROVIDENT FUND SECTION IN ACCOUNTS DEPARTMENT, FIRST FLOOR OF ADMINISTRATIVE BLOCK @ CMC, TOWN CAMPUS.						
TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
35	2.00	Nos	Supplying and fixing of Supreme make PVC nahini plain floor trap of 110mm dia. with S.S round jally including cost of cement solvent for joining,cement mortar for fixing in position etc., complete.		1No	
36	3.00	Nos	Supplying and fixing in position of Parryware White glazed wash hand basin 550x400mm including all fittings such as 1" SS brackets,15mm dia CP pillar cock (plumber make)1st quality inlet nylon connection,CP waste coupling, etc., complete.		1No	
37			Supplying and fixing in position of following types of bath room fittings of approved make including cost of all materials and required specials etc., complete.			
a	5.00	Nos	15mm dia CP Angle cock for WHB		1No	
b	5.00	Nos	CP Bottle trap		1No	
c	5.00	Nos	15mm dia CP open stop cock.		1No	
d	5.00	Nos	15mm dia CP short body bib cock		1No	
38	5.00	Nos	Supplying and Fixing in position of Chromium plated towel rod 600mm long with required teak wood plugs and screws including cost of all material etc., complete.		1No	
39	5.00	Nos	Supplying and fixing in position of mirror of size 600 x 450 mm with hard board back & plastic frame alround including cost of all materials and required screws etc. complete.		1No	
40	1.00	No	Supplying and fixing in position of ISI Elco brand gun metal Gate valve heavy duty 25mm dia including cost of all materials and required specials etc., complete.		1No	
41	545.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over new/old walls and ceilings with one coat of water based primer after preparation of the surface smooth and even with Birla wall care putty/ approved equivalent including cost of all materials, proper roller finish, brush etc. complete.		1M ²	
42	20.00	M ²	Painting two coats with exterior acrylic emulsion paint of approved make and colour over old/new walls and ceiling with one coat of exterior water based primer incl, cleaning the surfaces, cost of all materials, brush and scaffolding etc complete.		1M ²	
43	65.00	M ²	Painting one coat using synthetic enamel paint of approved make & color over the old woodwork including painting the furniture fittings where required surface preparation with application of putty, cost of all materials, brush & scaffolding etc. complete.		1M ²	
44	30.00	M ²	Painting two coats with synthetic enamel paint of approved make and colour over new wood works with one coat of wood primer incl. surface preparation with application of putty cost of all materials, brush and scaffolding etc. complete.		1M ²	
45	35.00	M ²	Painting one coat using synthetic enamel of approved make & colour over the old ironwork incl. surface preparation, necessary putty, cost of all materials, brush and scaffolding etc complete.		1M ²	
46	-		Painting new G.I. pipes with three coats consisting of one coat of zinc chromate primer and two coats of Ist quality synthetic enamel paint of approved make and colour incl. cleaning the pipes, cost of all materials and brush etc. complete.			
a	12.00	RM	15mm dia		1RM	

NAME OF THE WORK: RENOVATION OF BANKING, BILLING, CASH SECTION, COST ACCOUNTS AND PROVIDENT FUND SECTION IN ACCOUNTS DEPARTMENT, FIRST FLOOR OF ADMINISTRATIVE BLOCK @ CMC, TOWN CAMPUS.						
TENDER SCHEDULE						
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
b	12.00	RM	20mm dia		1RM	
c	8.00	RM	25mm dia		1RM	
d	8.00	RM	32mm dia		1RM	
47	635.00	M ²	Scraping completely and cleaning the white (or) colour washed surface (or) snowcem surface of old walls and ceilings using putty plate, sand paper and wire brush etc. incl. scaffolding and clearing the debris away from site etc. complete. (For Interior and Exterior surfaces).		1M ²	
48	5.00	RM	Supplying and fixing in position of 25mm dia (OD) MS powder coated curtain rod 20 gauge of approved make and colour including cutting cost of all materials etc., as directed by the engineer.		1RM	
49	6.00	Nos	Supplying and fixing in position of MS powder coated curtain brackets of approved make and colour with necessary wooden plugs/ supports and screws including cost of all materials etc., as directed by the engineer.		1No	
50	0.75	M ²	supplying and fixing in position of pelmet 150mm high with top open using 18mm thick OSL MDF exterior grade with 20x12mm t.w. beadings for top & bottom all-round including cost of all materials, t.w. plugs, screws and nails, beading, polishing etc. complete. (Curtain rod not included)		1M ²	
51	118.00	M ²	Providing & fixing "DAIKEN" gypsum ceiling tiles 9mm thick with Aluminium foil laminated on one side and PVC sheet laminated on the other side with hot dipped galvanised steel grid work , surface chemically cleaned capping PVC finished inbacked polyester paint, main tees of size 33(H) x 24mm every 1.20m centre to centre, stiched cross tee at 0.60m centre to centre to form a grid of size 600x600mm & suspending the grid from roof using 3mm GI rod, 6mm nylon, rawl plug & I bolt at every 1200 intervals laying "DAIKEN" gypsum 155 ceiling tiles of size 600x600mm over the formed grid having fire rating of 60 minutes as per BS 479/23 of 1987, light reflection of 85%		1M ²	
52	167.00	M ²	Supplying, laying and fixing in position of vinyl flooring of approved make and colour including cost of all materials, surface preparation, vamicol rubber based RB 1003 adhesive without formation of air bubbles & to avoid more sheet joints, welding the joints with PVC welding of matching colour and fixing including Welding rod, skirting 100mm PVC Coving, self levelling (3mm Tk.), and fixing and finishing in all respects etc., complete. as per manufacturer's standard specification.		1M ²	
53	5.00	Lorry loads	Transporting the debris by lorry from CMC Town Campus to outside of the campus including loading and unloading charges etc. complete.(Capacity 5.50 M ³ per lorry load).		1 Lorry load	
				Sub Total		
				CGST 9%		
				SGST 9%		
				Total Amount		