

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
1	12.00	M ³	Demolishing of existing brick walls in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
2	75.00	Nos	Labour charges for removing the existing doors, windows & clerestory windows, Cupboards, Fixed Glazing windows (steel / wood), ventilators, underneath CB (frame with shutters) complete set without any damage including all available fittings and the re-fitting items to be stored in contractor's safe custody & the remaining unusable items to be handed over to disposal directed. Of area 3 sq. metres and below		1No	
3	5.00	Nos	Labour charges for removing the existing M.S.Grills complete set without any damage including all available fittings and the re-fitting items to be stored in contractor's safe custody & the remaining unusable items to be handed over to disposal directed.		1No	
4	200.00	RM	Labour charges for removing the existing GI/PVC pipes upto 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges.		1RM	
5	200.00	RM	Labour charges for removing the existing GI/PVC pipes above 75mm dia including all available specials , without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1RM	
6	17.00	M ²	Labour charges removing the existing ACC roof sheet completely without any damage including all available accessories and clearing the debris away from site and the unserviceable items shall be disposed of as directed. The rate inclusive of required lead and lift charges .		1M ²	
7	15.00	Nos	Labour charges for removing the existing Grab rail rods, without any damage incl. available fittings and the same to be handed over to disposal as directed.		1No	
8	10.00	Nos	Labour charges for removing the existing various dia wheel valve/Gate valve/ open stop cock etc. with all available specials without any damage and the same to be handed over to disposal as directed.			
9	100.00	M ²	Labour charges for dismantling precast concrete or stone slab including clearing the debris away from site as directed. Thickness above 40 mm up to 75 mm		1M2	
10	23.00	Nos	Labour charges for removing the existing wash hand basin/sink with all available fittings complete set without any damage as directed.		1No	
11	18.00	Nos	Labour charges for removing the existing IWC/EWC with flush tank complete set including all available fittings and specials as directed.		1No	
12	280.00	M	Labour charges for removing the existing MS/SS curtain rods/pellets/wall guards/door guards/corner guards without any damage incl. available fittings and the re-fixing items to be stored in contractor's safe custody ,remaining handed over to deptl.store/disposal as directed		1RM	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
13	50.00	Nos	Labour charges for removing the existing towel rod/ towel rings/mirrors/paper trays/grab rail /shower rose/soap holders/cloth holders/urinal pan with stand or any other usable accessories complete set without any damage including all available fittings and the usable items to be handed over to depl.store and the un-usable items handed over to disposal as directed.		1No	
14	25.00	Nos	Labour charges for removing the existing brass/CP/PVC taps without any damage and the same to be handed over to disposal as directed.		1No	
15	1.00	M ³	Labour charges for Chipping / removing the existing grano flooring without affecting the adjacent area including clearing the debris away from site as directed.		1M ³	
16	25.00	M ³	Labour charges for demolition of brick jelly lime concrete from existing floor completely including clearing the debris away from site as directed.		1M ³	
17	10.00	M ²	Dismantling wooden boardings in lining of walls, Working Table top,,etc., including stacking within 50 metres lead complete set without any damage and the same to be handed over to depl.store as directed.		1M ²	
18	740.00	M ²	Labour charges for demolition of mosaic Cast-in-situ dadoing from walls, mosaic tiles with bed mortar from floor and mosaic skirting tiles from walls including clearing the debris away from site as directed.		1M ²	
19	590.00	M ²	Labour charges for chipping and removing the existing cement plastering from wall surface and wherever necessary and clearing the debris away from site as directed.		1M ²	
20	350.00	M ²	Labour charges for chipping and removing the ceramic/ glazed tiles, Kotah & Grante in CM from existing walls and floor including base plastering and clearing the debris away from site as directed.		1M ²	
21	1.00	M ³	Labour charges for demolition of existing RCC works and including cutting of all reinforcement bars completely by manually/ mechanical means without affecting the adjacent structure including stacking of steel bars & clearing the debris away from site, as directed.		1M ³	
22	10.00	M ²	Labour charges for dismantling of existing aluminium/ Gypsum/wooden partitions and false ceiling completely without any damage with all available accessories including clearing the debris away from site and the same to be handed over to depl.store/disposal as directed.		1M ²	
23	0.75	M ³	Plain Cement concrete 1:4:8 using 40mm size HBG machine broken jelly,M-sand including mixing in mixer machine, laying, consolidation and curing etc. complete for ramp to wheel chair access toilet from corridor.		1M ³	
24	10.00	M ²	Supplying, fixing and removing of steel form work in line and level with materials as indicated for RCC elements at locations as stated, including all props, struts, sealing all joints between sheets to prevent leakage of slurry, treating the surface with approved oils and removing the formwork. .		1M ²	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
25	1.00	M ³	Reinforced cement concrete M20 of nominal volumetric mix of 1:1.50:3.00 using 20mm down graded HBG machine broken jelly free from flakes and M-sand incl. mixing in mixer machine, laying, consolidation using vibrator, cost of all materials, curing etc. complete but excl. cost of steel reinforcement and form work.		1M ³	
26	600.00	Kgs	Supplying fabricating,placing and tying in position of steel reinforcement including cost of 18 gauge MS binding wire etc.complete.for all RCC works		1Kg	
27	0.50	M ³	Casting and fixing in position of RCC 1:2:4 for precast lintel using 20mm size HBG machine broken jelly, M-sand incl. mixing, laying, consolidation, curing, cost of all materials, necessary mould and platform etc. complete but excl. cost of steel and fabrication		1M ³	
28	3.00	M ³	Casting and fixing in position of RCC 1:2:4 for precast slabs using 3 to 8mm size HBG machine broken chips, M-Sand including cost of all materials, necessary mould and platform, smooth finishing with CM 1:3 for all exposed surfaces and curing etc. complete but excluding cost of steel and fabrication.		1M ³	
29	135.00	M ²	Toilet Water proofing : Supplying and applying toilet and skirting water proofing treatment by using hydro carbon free liquid applied elastomeric water proofing membrane like brush bond type of (a)Fosarc-Nitoproof -600PF having 2 coats of minimum wet film thickness of each coat 1.50mm including filling of cracks in floor/wall,grouting the junction of wall and floor,making grooves for inserting water proof membrane etc.,complete as per manufacturer's instructions and technical data sheet.(b)Supplying and fixing in position of toilet floor and skirting with single layer of white colour plain 45GSM filler glass mesh for proper water proofing of approved sample shall be provided before applying protective first coat and second coat of plastering including cost of all materials,properly stretched and nailed,ensuring equal thickness of plaster on both floor and walls sides of mesh. (c)Applying protective coats of plastering with 2 coats consist of base and top plastering with 1:3,8mm and 12mm thick respectively in 2 succesive layers etc.,complete. Incl.cost for Surface preparation, wastage, curing,etc, measurement shall be on the basis of net area water proofed.include drying and cleaning the surface free of dust, proper water ponding test,leakage points if any found with PU grout etc.The actual area treated shall be measured and paid.No extra shall be paid for any fillets,grooves or rounding. The contractor shall provide a performance guarantee for five-5 years on stamp paper in an approved form.		1M ²	
30	24.00	M ³	Cement concrete 1:4:8 using 20mm size brick jelly for toilet filling to a required height incl. cost of all materials, mixing , laying, consolidation and curing etc. complete.		1M ³	
31	4.00	M ³	Brick wall in Cement-mortar 1:6, 230mm and above thick using non-metric bricks of size 230x115x75mm (chamber burnt)including cost all materials and curing etc., complete. super structure up to floor v level		1M ³	
32	5.50	M ²	Brick work in CM 1:4 for partition wall using non-metric bricks of size 230x115x75mm(chamber burnt) including cost of all materials, labour for placing 2nos - 6mm dia MS rods at every 3rd course and curing etc. complete (steel will be measured separately).		1M ²	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
33	50.00	M ²	Brick on edge work in CM 1:4 using non-metric bricks of size 230x115x75mm(chamber burnt) including cost of all materials and curing etc. complete for cupboard, working platform support walls.		1M ²	
34	135.00	M ²	Plastering with CM 1:5, 12mm thick over new surface of internal Brick walls including cost of all materials and curing etc. complete.		1M ²	
35	10.00	M ²	Plastering with CM 1:3, 12mm thick for all RCC exposed surfaces to ceiling roof projections incl. cost of all materials,hacking, neat finishing and curing etc. complete		1M ²	
36	10.00	M ²	Plastering with CM 1:5, 20mm thick over external surface of new brick walls including providing grooves as required, cost of all materials and curing etc. complete in all floors at all heights.		1M ²	
37	910.00	M ²	Base Plastering with CM 1:5, 20mm thick over chipped surface of existing brick walls including cost of all materials and curing etc. complete.		1M ²	
38	15.00	M ³	Encasing with cement concrete 1:3:6, using machine broken HBG chips 10 to 12mm size to PVC pipes in toilet pits and wherever necessary incl. cost of all materials, necessary shuttering, laying, consolidation and curing etc. complete.		1M ³	
39	18.00	M ³	Screed concrete PCC 1:3:6 using 3to8mm size HBG machine broken chips, coarse sand including cost of all materials ,mixing, laying,consolidation and curing etc., complete under floor wherever necessary to eliminate the undulations.		1M ³	
40	700.00	M ²	Supplying and fixing of Vitrified/ceramic tiles ,1st quality 600x600mm size of approved make and colour set in CM 1:3, base including grouting the joints with epoxy grout of matching color tile mate/approved equivalent mixing with colour pigments, base with 2mm spacers in both direction including grouting the joints to matching colour, cost of all materials,cleaning and curing etc. complete for floor. (Basic rate tile-Rs.-600.00- / 1M²-Excl.GST-18%)		1M ²	
41	85.00	M ²	Supplying and laying of Non-skid Vitrified/Ceramic plain tiles, 1st quality 300X300mm size of approved make and colour set in CM 1:3, base with 2mm spacers in both direction including grouting the joints with epoxy grout of approved make and matching colour, giving proper slope, cleaning and curing etc. complete for toilet floor .(Basic rate of tile Rs.600.00 / 1M²-Excl.GST-18%)		1M ²	
42	910.00	M ²	Supplying and fixing of Glazed Plain wall tiles 1st quality 300x450mm/300x600mm size of approved make and colour set in CM 1:3 base including pointing with white cement mixed with colour pigments, providing best quality PVC corner edge beads, cleaning and curing etc. complete for dadoing. (Basic cost of tiles :- Rs.450.00/1M²-Excl.GST-18%)		1M ²	
43	500.00	M ²	Add Extra for providing tile Adhesive for fixing Glazed/ Ceramic / Vitrified Wall tiles with cement based high polymer modified quick set tile adhesive (water based) conforming to IS:15477, in average 3mm thickness at corridor walls and wherever necessary as directed by the Engineer-in-charge.		1M ²	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
44	13.50	M ²	Supplying and fixing in position of highly polished Granite slab 18 to 20mm thick of approved quality and approved sample, set in CM 1:3, including cost of all materials, pointing white cement with matching colour pigments, cleaning and curing etc. complete. for Table Top (Basic rate of granite Rs.2,000.00 / 1M²-Excl.GST-18%).		1M ²	
45	1.00	No	Providing opening of required size & shape for wash basins/ kitchen sink in kitchen platform, vanity counters and similar location in marble/Granite/stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete.		1No	
46	15.00	M	Providing full nosing to exposed edges of granite in table top etc.complete		1RM	
47	15.00	M	Providing half nosing to exposed edges of granite in table top etc.complete		1RM	
48			Supplying and fixing in position of following types of wooden Doors frame with shutters including cost of all furniture fittings etc complete as per Sketch and Specifications.			
a	5.25	M ²	D1 -Door 1200X2100MM		1M ²	
b	2.75	M ²	D2- Door 1200X2100MM		1M ²	
c	5.75	M ²	D3 -Door 1350X2100MM		1M ²	
d	16.00	M ²	D4- Door 750X2100MM		1M ²	
e	2.85	M ²	W1-Window 1920X1460		1M ²	
f	QRO	M ²	W1a-Window 1920X1460		1M ²	
g	QRO	M ²	W1b-Window 1920X1460		1M ²	
49	2.00	M ²	Supplying and fixing in position of Aluminium Fixed Glazing of following sizes in all floors including cost of all furniture fittings etc complete. as per Sketch and Specification- FG-1200X600MM		1M ²	
50	4.48	M ²	Supplying and fixing in position of Aluminium door frame with shutter of following sizes incl. cost of all furniture fittings etc complete. as per Sketch and Specification-Aluminium Partition Cum Door		1M ²	
51			Supplying and fixing in position of following Wooden Cup boards incl. cost of all furniture fittings etc complete. as per Sketch and Specification			
a	6.80	M ²	Cupboard -CB(Size-1620X2100MM)		1M ²	
b	15.37	M ²	Cupboard -CB1(Size-915X2100MM)		1M ²	
c	4.41	M ²	Cupboard -CB2(Size-1050X2100MM)		1M ²	
d	5.00	M ²	Underneath Cupboard-UCB(910X610X820MM)		1M ²	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
52	100.00	Kgs	Supplying and fixing in position of MS grill with outer frame,approved design using Ms flats,square rods including cost of all materials,fabrication charges,1 coat of yellow oxide primer and two coat powder coated paint etc., complete (MS Grill will be fixed seperately for alu.windows wherever necessary so as to provided with necessary openings for window closing and opening)		1Kg	
53	18.00	Nos	Supplying, transporting to Site , Unloading , Safe storage, installing, testing and commissioning of White colour EWC with "S/P " trap parryware make with solid plastic seat cover(heavy type) , pan connector etc.complete. Cost including conveyance of all materials to the site, all labour charges etc., complete including cutting and making rough finishing the walls and floors wherever required,checked and directed by the Engineer-in-charge.		1No	
54	18.00	Nos	Supplying and fixing in position of Slimeline combiflush twin flush type plastic cistern (white) for EWC including required fittings such as 1st quality inlet nylon connection,pvc flushing pipe etc., complete.		1No	
55	2.00	Nos	Supplying, transporting to Site , Unloading , Safe storage, installing, testing and commissioning of Parryware White glazed wash hand basin 550x400mm including all fittings such as SS pipe brackets/S.S Rag bolts set , 15mm dia CP pillar cock (plumber make),1st quality inlet nylon connection,CP waste coupling, PVC waste pipe etc., complete. Cost including conveyance of all materials to the site, all labour charges etc., complete.		1No	
56	1.00	No	Supplying and fixing in position of Porcelain sink 600x450x250mm size including cost of all fittings such as ,CP waste coupling etc., complete.		1No	
57	1.00	No	Supplying and making of Bed Pan stainless steel sink using 304 grade 16G stainless steel sink, 100mm dia S.S. pipe 18G with flange and fabricated 14G stainless steel 'P' trap with flange including cost of all materials (excluding cost of flush tank) 1/2" S.S. pipe (304 grade 16G) at around sink inner for flushing, bolts and nuts, necessary washer for connecting S.S. "P" trap and S.S. sink etc., Complete.(Size:600X450X300mm)		1No	
58	1.00	No	Supplying and fabrication of Stainless Steel fabricated,factory made customized counter mount Deep Sink with CP brass chain with rubber plug,50mm CP brass waste Coupling,50mm thk.PVC ball valve etc.,Complete .(Size:750X600X600)		1No	
59	5.00	Nos	Supplying and fixing of Supreme make PVC nahini plain floor trap of 110mm dia. with S.S round jally including cost of cement solvent for joining,cement mortar for fixing in position etc., complete.		1No	
60	18.00	Nos	Supplying and fixing of 110mm dia Supreme make PVC multi floor trap with S.S. hinged type square of cement solvent for joining,cement mortar for fixing in position etc., complete.		1No	
61			Supplying and fixing in position of following types of bath room fittings of approved make including cost of all materials and required specials etc., complete.			
a	20.00	Nos	15mm dia CP long body bib cock		1No	
b	36.00	Nos	15mm dia CP Angle cock for WHB & flush tank.		1No	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
c	2.00	Nos	15mm dia CP Two way bib cock with health faucet		1No	
d	18.00	Nos	CP Bottle trap		1No	
e	18.00	Nos	15mm dia CP open stop cock.		1No	
f	9.00	Nos	15mm dia CP short body bib cock		1No	
g	18.00	Nos	15mm dia CP Two way bib cock with health faucet		1No	
h	5.00	Nos	15mm-PVC-shower rose		1No	
62	2.00	Nos	Supplying and fixing in position of 15mm dia CP brass Elbow operated clinical Bib cock with Wall Flange including cost of all material and required specials etc., complete.		1No	
63	20.00	Nos	Supplying and Fixing in position of Chromium plated towel rod 600mm long with required teak wood plugs and screws including cost of all material etc., complete.		1No	
64	20.00	Nos	Supplying and fixing in position of Chromium plated soap tray with required teak wood plugs and brass screws including cost of all material etc., complete.		1No	
65	10.00	Nos	Supplying and fixing in position of mirror of size 600 x 450 mm with hard board back & plastic frame around including cost of all materials and required screws etc. complete.		1No	
66			Supplying and fixing in position of ISI Elco brand gun metal Gate valve heavy duty including cost of all materials and required specials etc., complete.			
a	10.00	Nos	25mm dia		1No	
b	10.00	Nos	32mm dia		1No	
c	10.00	Nos	40mm dia		1No	
67			Supplying and fixing in position of Zoloto make Butterfly valve with G.I flange, bolt & net , including cost of all materials and required specials etc... complete.			
a	5.00	Nos	50mm dia		1No	
b	5.00	Nos	65mm dia		1No	
68	15.00	M	Supplying and fixing in position of edge protection angle using Aluminium angle 40x25x3mm in toilet area (or) other areas wherever required in the level difference found in floor level etc,complete.		1RM	
69			Supplying and fixing of the following PVC pipes including cutting charges, cost of cement solvent for joining and fixing with necessary specials, cost of all materials etc., complete for internal pipe lines. (ABOVE GROUND LEVEL)			
a	50.00	M	40mm dia 6Kgs/CM2 (incl. specials)		1RM	
b	50.00	M	50mm dia 6Kgs/CM2 (incl. specials)		1RM	
c	50.00	M	63mm dia 4Kgs/CM2 (incl. specials)		1RM	
d	50.00	M	75mm dia 4Kgs/CM2 (incl. specials)		1RM	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
e	75.00	M	110mm dia 4Kgs/CM2 (incl. specials)		1RM	
70			Supply and Installing at site PVC SWR Pasted pipe using Solvent Cement ISI Marked [As per IS 13592] with PVC special fittings , Plain Bends, Door bends, Couplers, Reducers, Single Tees, Door Tees, Double Tees, Reducing Tees, Plain Ys, Door Ys, Double Ys, Elbows , Door Elbows etc. Adapters, Air vents, Clamping with GI U Clamps as required for firmly installing the pipes. Testing of the system for leakage and Air tightness (Make: Ashirwad,Supreme, Finolex or approved equivalent) excluding cost of MS brackets which will be paid seperately.			
a	25.00	M	75mm dia - Type-B (incl. specials)		1RM	
b	25.00	M	110 mm dia - Type-B (incl. specials)		1RM	
71	100.00	Kgs	Supplying and fixing of required size brackets and clamps using MS Angles, MS flats, and MS threaded rods as instructed by Engineer including one coat of metal primer, two coats with synthetic enamel paint making holes in wall for fixing cement concrete for packing finishing the surfaces etc., complete		1Kg	
72			Supplying of G.I special clamp with coach screw, U bolt , nut & washer of the following sizes of G.I Pipe supports and specifications etc. complete.			
a	15.00	Nos	100 mm length		1No	
b	20.00	Nos	230 mm length		1No	
73			Supplying , cutting,threading, laying and joining of G.I. pipes ' B ' class ISI make with necessary ' UNIK' make specials including cost of all required materials, clamps, teak wood plugs and screws etc., complete. (ABOVE GROUND LEVEL)			
a	50.00	M	15mm dia		1RM	
b	50.00	M	20mm dia		1RM	
c	50.00	M	25mm dia		1RM	
d	25.00	M	32mm dia		1RM	
e	20.00	M	40mm dia		1RM	
74			CPVC SDR 11 Piping System (water supply:Domestic water,flushing, Hot water, RO water, Soft water piping system) : Supply and Installing at site Concealed CPVC SDR 11 ASTM D 2846 Pipes (Equivalent Standard Size) with suitable CPVC Schedule 80 fittings (Ts, Elbows, Bends, Reducers, Couplers, Ys etc.) Adapters, Clamping with GI U Clamps as required for firmly installing the pipes, having thermal stability for Hot and Cold Water supply. Joined using Solvent Cement fittings with metal inserts suitable for the working pressure. Hydrostatic Testing of the Pipes using necessary test pressure for specified time period etc. (Make: Ashirwad, Supreme / Ajay / Astral or approved equivalent)			
a	50.00	M	15mm dia		1RM	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
b	50.00	M	20mm dia		1RM	
c	50.00	M	25mm dia		1RM	
d	50.00	M	32mm dia		1RM	
75	20.00	Nos	Supplying and fixing in position of stainless steel pipe grab rail 25mm dia 18 gauge, 304 grade including cost of all materials, bending to required shape fixing, grouting with CM finishing in all respects etc. complete (total length 0.460m).		1No	
76	50.00	M	Supplying and fixing in position of stainless steel pipe hand rail 50mm dia 16 gauge, 304 grade including cost of all materials, bending to required shape fixing, grouting with CM finishing in all respects etc. complete		1RM	
77	150.00	M	Providing and fixing of fastrack Curtain Track hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon heavy type hooks,necessary screws for track system and cost of all materials cost of labour and Transportation,etc.complete.		1RM	
78	30.00	M	Providing and fixing of fastrack I.V track-hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon heavy type hooks which is capable to hold the weight atleast 20kgs per stand ,necessary screws for track system and cost of all materials cost of labour and Transportation,etc.complete.		1RM	
79	25.00	Nos	Providing and fixing of fastrack I.V . stand- hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon hooks,necessary screws for track system and cost of all materials,cost of labour and transportation,etc		1No	
80	10.00	M	Supplying and fixing of stainless steel curtain rods frame work using 25mm dia SS pipe 16 SWG, 304 grade incl. labour charges for fixing and polishing, cost of end PVC bushes etc. as per Engineer's instructions		1RM	
81	20.00	Nos	Supplying and fixing of stainless steel curtain ring of 38mm dia for frame work including polishing etc. as per Engineer's instructions		1No	
82	10.00	M	Supplying and fixing in position of 25mm dia (OD) MS powder coated curtain rod 20 gauge of approved make and colour including cutting cost of all materials etc., as directed by the engineer		1RM	
83	50.00	Nos	Supplying and fixing in position of MS powder coated curtain brackets of approved make and colour with necessary wooden plugs/ supports and screws including cost of all materials etc., as directed by the engineer.		1No	
84	50.00	M	Supplying and fixing in position of Salem stainless steel angle 65x65mm - 304 grade 18 gauge corner guard,embedded type required height wherever necessary including cost of all materials,drilling holes, screws and nails etc. complete.		1RM	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
85	30.00	M	Supplying and fixing in position of plain open type Salem stainless steel angle 50x50mm - 304 grade 18 gauge corner guard, required height wherever necessary including cost of all materials,drilling holes, screws and nails etc. complete.		1RM	
86	25.00	M	Supplying and fixing in position of Salem stainless steel angle 304 grade 18 gauge corner guard,embedded type required size & height wherever necessary including cost of all materials,drilling holes, screws and nails etc. complete.		1RM	
87	10.00	M ²	Supplying and fixing in position of wall glazing work using polished stainless steel sheet 18 gauge SS 304 grade ,300mm height with back 12mmplywood incl. cost of all materials teak wood plug, screws & nails etc complete as per Engineers instructions .		1M ²	
88	15.00	M2	Supplying and fixing in position of Door glazing work using polished stainless steel sheet 18 gauge SS 304 grade ,incl. cost of all materials screws & nails etc complete as per Engineers instructions.		1M ²	
89	10.00	Nos	Supplying and fixing in position of Hydraulic door closer (Rolex Make) to wooden/aluminium doors complete set including required screws and nails etc., complete.		1No	
90	10.00	M ²	Supplying and fixing in position of 12mm thk bothside laminated MDF duratuff board covering /closings to existing openings (or) match the diffrence level of wall thickness with necessary screws, nails & accessories etc., complete. (For windows ,doors,ventilators and door cum partitions)		1M ²	
91	10.00	M ²	Supplying and fixing in position of 12mm thick plywood covering /closings to existing openings (or) match the diffrence level of wall thickness with necessary screws, nails & accessories etc., complete. (For windows ,doors,ventilators and door cum partitions)		1M ²	
92	1,000.00	M ²	Scraping completely and cleaning the white (or) colour washed surface (or) snowcem surface of old walls and ceilings using putty plate, sand paper and wire brush etc. incl. scaffolding and clearing the debris away from site etc. complete.(For Interior and Exterior surfaces).		1M ²	
93	200.00	M ²	White cement Washing two coats over old/new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and curing etc. Complete.		1M ²	
94	175.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over new walls and ceilings with one coat of water based primer after preparation of the surface smooth and even with Birla wall care putty/ approved equivalent including cost of all materials, proper roller finish, brush etc. complete.		1M ²	
95	1,000.00	M ²	Painting one coat using Acrylic emulsion paint of appd. Make & colour over old painted surfaces of walls & ceilings incl. surface preparation with necessary putty, Brush, cost of all materials & scaffolding etc. Complete.		1M ²	
96	20.00	M ²	Painting two coats with exterior acrylic emulsion paint of approved make and colour over new walls and ceiling with one coat of exterior water based primer incl, cleaning the surfaces, cost of all materials, brush and scaffolding etc complete.		1M ²	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
97	100.00	M ²	Painting two coats with synthetic enamel paint of approved make colour over old / new walls with one coat of oil based primer after preparation of the surface smooth and even with Birla wall care putty / approved Equivalent including cost of all materials, coat of white cement base, brush and scaffolding etc. Complete.		1M ²	
98	100.00	M ²	Painting two coats using synthetic enamel paint of approved make & colour over the old painted surface of walls & ceilings incl. Surface preparation, cost of all materials, necessary putty , brush & scaffolding etc. Complete		1M ²	
99	250.00	M ²	Painting one coat using synthetic enamel paint of approved make & color over the old painted surface of walls & ceilings incl. Surface preparation, cost of all materials, necessary putty , brush & scaffolding etc. Complete.		1M ²	
100	750.00	M ²	Painting one coat using Acrylic distemper of approved make and colour over old surface of walls & ceilings incl. surface preparation with necessary putty, cost of all materials, brush and scaffolding etc. complete.		1M ²	
101	175.00	M ²	Painting one coat using synthetic enamel paint of approved make & color over the old woodwork including painting the furniture fittings where required surface preparation with application of putty, cost of all materials, brush & scaffolding etc. complete.		1M ²	
102	20.00	M ²	Painting two coats with synthetic enamel paint of approved make and colour over new wood works with one coat of wood primer incl. surface preparation with application of putty cost of all materials, brush and scaffolding etc. complete.		1M ²	
103	25.00	M ²	Painting one coat using synthetic enamel of approved make & colour over the old ironwork incl. surface preparation, necessary putty, cost of all materials, brush and scaffolding etc complete.		1M ²	
104	25.00	M ²	Painting two coats with synthetic enamel paint of approved make & colour over the new ironwork including surface preparation, necessary putty, cost of all materials, brush and scaffolding etc. complete		1M ²	
105			Painting two coats with synthetic enamel paint of approved make and colour over GI pipes with one coat of zinc chromate including cleaning the pipes, cost of all materials, brush, scaffolding etc. Complete.			
a	50.00	M	15mm dia		1RM	
b	50.00	M	20mm dia		1RM	
c	50.00	M	25mm dia		1RM	
d	25.00	M	32mm dia		1RM	
e	20.00	M	40mm dia		1RM	
106	100.00	Kgs	Supplying, fabrication and erection of roof truss & purlin using of MS Pipe, S.H.S, Angle & Plate, 'B' class Apollo/equivalent charges including Cost of necessary tools & materials, labours, fabrication and welding Charges ,one coat primer & 2 coat of enamel paint as per instruction of engineer in charge, complete		1kg	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
107	8.00	M ²	Providing and fixing precoated galvalume iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.		1M ²	
108			Making through holes in Plain or Reinforced Cement Concrete /Brickwork with Diamond Core Drilling System by using BOSCH power tools of following diameter.			
a	5.00	Nos	upto 200mm (Plain or Reinforced Cement Concrete) thickness upto 250mm		1No	
b	5.00		upto 200mm (Brickwork) thickness upto 250mm		1No	
109	5.00	Nos	Drilling suitable holes in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 200mm in RCC beam/lintes/slabs including fixing the steel bars in position using epoxy resin anchor grout of approved make but excluding the cost of reinforcement , at all levels complete as per direction of Engineer in-charge.for upto dia16mm dia-lintel dowel rods from RCC members which can be grouted with Fosroc epoxy resin anchor grout/approved equivalent make.		1No	
110	2.00	Nos	Bore Packing around the pipes in Brick walls and Concrete members applying bonding agent of SBR Latex or approved equivalent around the internal partition of surface, Quick setting component of Rendroc plug/approved equivalent packed externally and the gaps around the pipe tightly packed with GP2 Chemical. Provide the backer rods if the gap around the pipe have more than 25mm including cost of all materials, labour charges, neat finishing, curing, etc., complete. (Note : Water to be stagnated around the bore packing about 48 hours and water leakage has to be cleared from Engineer in charge.)		1No	
111	20.00	Nos	Towards the Labour charges for engaging Helpers for intercarting the department office furnitures stored at identified locations so as to provide access and clearance for work front and cleaning the tables prior to handing over the user department as per the direction of the Engineer in charge.		1No	
112	5.00	Nos	Providing minor repair charges to the existing door,windows,ventialtors and cupboards including replacement of existing damaged furniture fittings with new one including removing and refixing,making them to functional condition, fixing and finishing in all repects as directed by the engineer-in-charge. (required furniture fittings, wooden scantlings and teak wood beadings will be supplied by dept.at free of cost-Rate applicable for all various sizes)		1No	

NAME OF THE WORK:MODIFICATION OF EXISTING GERIATRIC WARD IN O5-EAST- FIFTH FLOOR OF " O " BLOCK AT CMC ,TOWN CAMPUS.						
TENDER SCHEDULE						
SI.No	Quantity		Description of the work	Rate	Unit	Amount
113	10.00	M	Labour charges for refixing the existing curtain rods, pelmets, alu./ss/wooden corner guard & wall Guard without any damage incl. available fittings as directed.(Required curtain rods, pelmets, alu./ss/wooden corner guard & wall Guard will be supplied by dept.at free of cost)		1RM	
114	15.00	Nos	Labour charges for refixing the existing doors, windows, Ventilators Cupboards, Underneath and Hanging Cup boards (steel or wood) (Frame with shutters) complete set without any damage including all available fittings as directed.(Required doors, windows, Ventilators Cupboards, Underneath and Hanging Cup boards (steel or wood) (Frame with shutters) will be supplied by dept.at free of cost)		1No	
115	5.00	Lorry loads	Transporting the debris by lorry from CMC ,Town campus to outside of the campus including loading and unloading charges etc. complete.(capacity 5.50 M ³ /per lorry load).		1lorry load	
			Sub Total			
			CGST 9%			
			SGST 9%			
			Total Amount			