

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
1			Open wiring for light / calling bell / exhaust fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe /25mm Casing with necessary accessories like bend, nails etc including supply and fixing of 3 terminal ceiling rose / holder controlled by 10Amps one way Roma Plus Modular switch in existing metal box.(Neutral & Earth can be looped with in the same circuit)			
a	3	Pts	3.0 mts point		Pts	
b	6	Pts	4.5 mts point		Pts	
c	8	Pts	6.0 mts point		Pts	
2			Open wiring for Fan Point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe / 25mm Casing with necessary accessories Like bend, nails etc including supply and fixing of 3 terminal ceiling rose controlled by 10Amps one way Roma Plus Modular switch & with Socket Type Roma Plus Modular Regulator in existing metal box. (Neutral & Earth can be looped with in the same circuit)			
a	1	Pts	3.0 mts point		Pts	
b	2	Pts	4.5 mts point		Pts	
c	3	Pts	6.0 mts point		Pts	
3			Concealed wiring for light / calling bell / exhaust fan point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like bend, nails etc including supply and fixing of 3 terminal ceiling rose / holder controlled by 10Amps one way Roma Plus Modular switch in existing metal box.(Neutral & Earth can be looped with in the same circuit)			
a	20	Pts	3.0 mts point		Pts	
b	46	Pts	4.5 mts point		Pts	
c	67	Pts	6.0 mts point		Pts	

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C		TENDER SCHEDULE				
Sl.No			Description	Rate	Unit	Amount
4			Concealed wiring for Fan Point 2x22/.3mm (1.5sq.mm) PVC insulated unsheathed copper wire and 1x22/.3mm (1.5sq.mm.) PVC insulated unsheathed copper wire for earthing in 19mm dia 2mm thick rigid PVC conduit pipe with necessary accessories like bend, nails etc including supply and fixing of 3 terminal ceiling rose controlled by 10Amps one way Roma plus Modular switch & with Socket Type Modular Regulator in existing metal box. (Neutral & Earth can be looped with in the same circuit)			
a	1	Pts	3.0 mts point		Pts	
b	13	Pts	4.5 mts point		Pts	
c	26	Pts	6.0 mts point		Pts	
5	90	RM	Excess Length of wiring work above 6 meter for light/Exhaust Fan/Calling bell and fan point per meter		RM	
6	46	Nos	Supply and fixing of 'S' Hook on Ceiling including Plastering		Nos	
7	100	mtrs	Supply and Laying of 19mm dia 2mm thick PVC Conduit Concealed		mtrs	
8	80	mtrs	Supply and Laying of 25mm dia 2mm thick PVC Conduit Concealed		mtrs	
9	75	mtrs	Supply and Laying of 19mm dia 2mm thick PVC Conduit Pipe/ 25mm Casing Open		mtrs	
10	70	mtrs	Supply and Laying of 25mm dia 2mm thick PVC Conduit / 25mm Casing Open		mtrs	
11	280	RM	Open wiring for run of main using 6R x 2.5sqmm wire with 19mm dia 2mm thick PVC Pipe / 25mm Casing		RM	
12	210	RM	Open wiring for run of main using 3R x 2.5sqmm wire with 19mm dia 2mm thick PVC Pipe / 25mm Casing		RM	
13	320	RM	Open wiring for run of main using 6R x 4sqmm wire with 32mm dia 2mm thick PVC Pipe / 40mm Casing		RM	
14	240	RM	Open wiring for run of main using 3R x 4sqmm wire with 19mm dia 2mm thick PVC Pipe / 25mm Casing		RM	
15	60	RM	Open wiring for run of main using 4R x 10sqmm wire +1Rx10sqmm wire with 32mm dia 2mm thick PVC Pipe / 40mm Casing		RM	
16	50	RM	Open wiring for run of main using 4R x 16sqmm wire +1Rx16sqmm wire with 32mm dia 2mm thick PVC Pipe / 40mm casing		RM	
17			Wiring For Circuit/sub main wiring along with earth wire with the following size of FRLS PVC insulated copper wire in with out conduit as required following wires			

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
a	20	Rm	2x2.5sqmm+1x2.5sqmm Earth wire		Rm	
b	25	Rm	2x4.0sqmm+1x4.0sqmm Earth wire		Rm	
c	30	Rm	4x2.5sqmm +2x2.5sqmm wire		Rm	
d	45	Rm	4x4.0sqmm +2x4.0sqmm wire		Rm	
e	20	Rm	4x10.0sqmm +1x10sqmm Earth wire		Rm	
f	15	Rm	4x16.0sqmm +1x16sqmm Earth wire		Rm	
18			Supply and Fixing of Concealed Type Roma Plus Modular Metal switch Box with Module Cover plate including hardwares and connection etc as required			
a	5	Nos	Supply and fixing of 3 modular Roma Plus metal box with Roma Plus plate (Concealed) Including (1x10A modular Roma plus switch & 1x6A Roma plus Socket)		Nos	
b	30	Nos	Supply and fixing of 3 modular Roma Plus metal box with Roma Plus plate (Concealed) Including (1x20A Modular Roma plus switch & 1x16A Roma plus Socket)		Nos	
c	40	Nos	Supply and fixing of 6 modular Roma Plus metal box with Roma Plus plate (Cocealed) Including (2x10A Modular Roma plus switch & 2x6A Roma Plus Socket)		Nos	
d	30	Nos	Supply and fixing of 6 modular Roma Plus metal box with Roma Plus plate (Cocealed) Including (2x20A Modular Roma plus switch & 2x16A Roma Plus Socket)		Nos	
e	3	Nos	Supply and fixing of 12 modular Roma Plus metal box with Roma Plus plate (Cocealed) Including (3x20A Modular Roma Plus switch & 3x16A Roma Plus Socket)		Nos	
f	2	Nos	Supply and fixing of 12 modular Roma Plus Metal box with Roma Plus plate(Cocealed) Including (3x10A modular Roma Plus switch & 3x6A Roma Plus Socket with 3xDummy plate)		Nos	
19			Supply and Fixing of Concealed Type Roma Plus Modular Metal switch Box with Module Cover plate including hardwares and connection etc as required			
a	6	Nos	Supply and fixing of 1 modular box Metal box with Roma Plus plate (Concealed)		Nos	
b	6	Nos	Supply and fixing of 2 modular box Metal box with Roma Plus plate (Concealed)		Nos	
c	8	Nos	Supply and fixing of 3 modular box Metal box with Roma Plus plate (Concealed)		Nos	
d	6	Nos	Supply and fixing of 4 modular box Metal box with Roma Plus plate(Concealed)		Nos	
e	6	Nos	Supply and fixing of 6 modular box Metal box with Roma Plus plate(Concealed)		Nos	

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
f	4	Nos	Supply and fixing of 8 modular box Metal box with Roma Plus plate(Concealed)		Nos	
g	5	Nos	Supply and fixing of 12 modular box Metal box with Roma Plus plate (Concealed)		Nos	
20	3	Nos	Supply and Fixing of 4x4 Ms Box with Hylamsheet with 1x5A Switch & 1x5A Socket (Concealed)		Nos	
21			Supply and Fixing of Open Type Roma Plus Modular PVC Surface Box with Module Cover plate including hardwares and connection etc as required			
a	6	Nos	Supply and fixing of Moudlar Dummy plate		Nos	
b	3	Nos	Supply and fixing of 3 modular Roma plus Surface box with Roma Plus plate (Open) Including (1x10A modular Roma Plus switch & 1x6A Roma Plus Socket)		Nos	
c	3	Nos	Supply and fixing of 3 modular Roma Plus Surface box with Roma Plus plate (Open) Including (1x20A Modular Roma Plus switch & 1x16A Roma Plus Socket)		Nos	
d	4	Nos	Supply and fixing of 6 modular Roma Plus Surface box with Roma Plus plate (Open) Including (2x10A Modular Roma Plus switch & 2x6A Roma Plus Socket)		Nos	
e	6	Nos	Supply and fixing of 6 modular Roma Plus Surface box with Roma Plus plate (Open) Including (2x20A Modular Roma Plus switch & 2x16A Roma plus Socket)		Nos	
f	3	Nos	Supply and fixing of 12 modular Roma Plus Surface box with Roma Plus plate (Open) Including (3x20A Modular Roma Plus switch & 3x16A Roma Plus Socket)		Nos	
g	2	Nos	Supply and fixing of 12 modular Roma Plus Surface box with Roma Plus plate(Open) Including (3x10A modular Roma Plus switch & 3x16 Socket with 3xDummy plate)		Nos	
22			Supply and Fixing of Open Type Roma Plus Modular PVC Surface Box with Module Cover plate including hardwares and connection etc as required			
a	2	Nos	Supply and fixing of 1 modular box Surface box with Roma plate (Open)		Nos	
b	4	Nos	Supply and fixing of 2 modular box Surface box with Roma plate (Open)		Nos	
c	3	Nos	Supply and fixing of 3 modular box Surface box with Roma plate (Open)		Nos	

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
d	4	Nos	Supply and fixing of 4 modular box Surface box with Roma plate(Open)		Nos	
e	3	Nos	Supply and fixing of 6 modular box Surface box with Roma plate(Open)		Nos	
f	3	Nos	Supply and fixing of 8 modular box Surface box with Roma Plus plate(Open)		Nos	
g	2	Nos	Supply and fixing of 12 modular box Surface box with Roma Plus plate(Open)		Nos	
23	3	Nos	Supply and Fixing of 4x4 Ms Box with Hylamsheet with 1x5A Switch & 1x5A Socket (Open)		Nos	
24	50	RM	Supply and laying of 1RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Concealed)		RM	
25	20	RM	Supply and laying of 2RxLAN cable through 19mm dia 2mm thick PVC conduit pipe with necessary accessories like 3/4" PVC bends, nails etc. (Concealed)		RM	
26	20	RM	Supply and laying of 3RxLAN cable through 25mm dia 2mm thick PVC conduit pipe with necessary accessories like PVC bends, nails etc. (Concealed)		RM	
27	20	Rm	Supply and laying of 4RxLAN cable through 25mm dia 2mm thick PVC conduit pipe/ Casing with necessary accessories like PVC bends, nails etc. (Concealed)		Rm	
28	150	RM	Supply and laying of 1RxLAN cable through 19mm dia 2mm thick PVC conduit pipe / 25mm Casing with necessary accessories like PVC bends, nails etc. (Open)		RM	
29	230	RM	Supply and laying of 2RxLAN cable through 19mm dia 2mm thick PVC conduit pipe / 25mm casing with necessary accessories like 3/4" PVC bends, nails etc. (Open)		RM	
30	280	RM	Supply and laying of 3RxLAN cable through 25mm dia 2mm thick PVC conduit pipe / 25mm Casing with necessary accessories like PVC bends, nails etc. (Open)		RM	
31	320	Rm	Supply and laying of 4RxLAN cable through 25mm dia 2mm thick PVC conduit pipe / 25mm casing with necessary accessories like PVC bends, nails etc. (Open)		Rm	
32	90	Rm	Supply and Laying of 1RxLAN Cable through with out Conduit		Rm	
33	10	Nos	Supply and fixing of computer RJ-45 socket (AMP" make) including I/O box (Concealed)		Nos	
34	25	Nos	Supply and fixing of computer RJ-45 socket (AMP" make) including I/O box (Open)		Nos	

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
35	2	Nos	Supply and fixing of AC metal socket board provisions for fixing DP MCB including supply and fixing of 20A/32A ,C-Curve, 10KA,DP MCB "MDS" LEGRAND make box (Concealed) for AC		Nos	
36	4	Nos	Supply and fixing of AC metal socket board provisions for fixing DP MCB including supply and fixing of 20A/32A,C-Curve, 10KA, DP MCB "MDS" LEGRAND make box (Open) for AC		Nos	
37	2	Nos	Supply and fixing of Four pole Enclosure with 63A, C-Cure,10KA ,Four pole MCB(Open)		Nos	
38	2	Nos	Supply and fixing of Two pole Enclosure with 63A C-Cure,10KA ,Double pole MCB(Open)		Nos	
39	2	Nos	Supply and Fixing of 80A C-Cure,10KA, Four pole MCB in weather proof (Syntex box) Open		Nos	
40	3	Nos	Supply and installation of 3phase 8way double door 7 segment MCB DB MDS Legrand make (open) including 1no 63A 4 pole MCB 3 nos 63A DP RCBO 30ma, 24nos 6/10/16/20/32 SP MCBs Legrand Make, Code No:507887		Nos	
41	2	Nos	Supply and installation of 3phase 6way double door 7 segment MCB DB MDS Legrand make (Concealed) including 1no 63A 4 pole MCB 3 nos 63A DP RCBO 30ma, 18nos 6/10/16/20/32 SP MCBs Legrand Make, Code No:507886		Nos	
42	1	Nos	Supply and installation of Single phase 8way MCB DB MDS Legrand make (Concealed) including 1no 32A double pole MCB 1 no 6nos 6/10/16/20/32 SP MCBs Legrand Make, Code No:507887		Nos	
43	2	Nos	Supply and installation of Single phase 8way MCB DB MDS Legrand make (Open) including 1no 32A double pole MCB 1 no 6nos 6/10/16/20/32 SP MCBs Legrand Make, Code No:507611		Nos	
44	1	Nos	Supply and Fixing of 3 Phase 125A L&T Manual Change Over switch (Open)		Nos	
45	50	Rm	Supply and Laying of 3.5cx70sqmm Al/Ar Cable (Open)		Rm	
46	4	Nos	Supply anf Fixing of 3.5CX70sqmm suitable Gland End termination		Nos	
47	55	mtrs	Supply and Laying of 3.5cx16Sqmm Al/Ar Cable (Open)		mtrs	
48	8	Nos	Supply anf Fixing of 3.5CX16sqmm suitable Gland End termination		Nos	
49			Labour Charges for fixing of Following Items			
a	89	Nos	2'X2' Flase ceiling LED light fitting fixing Charges (Light Fitting & 2core wire will be Suppling By Department)		Nos	

NAME OF THE WORK: MODIFICATION IN KNICU WARD AS MICU @ SECOND FLOOR OF 'O' BLOCK IN CMC, TOWN CAMPUS						
SCHEDULE-C			TENDER SCHEDULE			
Sl.No			Description	Rate	Unit	Amount
b	35	Nos	4 feet Tube light fitting fixing Charges (Light Fitting & 2core wire will be Suppling By Department)		Nos	
c	26	Nos	3W Flase ceiling LED light fitting fixing Charges (Light Fitting & 2core wire will be Suppling By Department)		Nos	
d	41	Nos	48"/36" Ceiling fan with downrod arrangement fixing charges (Ceiling Fan & 2core wire will be Suppling By Department)		Nos	
e	4	Nos	12" Exhaust Fan with loovers Fixing charges (Exhaust Fan, loovers & 2core wire will be Suppling By Department)		Nos	
50	1	LS	Labour Charges For Removing and Rearranging of wiring,Switchbox,Light fiiting,Fan, DB and other electrical Items etc		LS	
				Sub Total		
Excl.GST-18% -C/O to Consolidated Summary						