

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
1	10.00	M ³	Demolishing of brick walls in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
2	5.00	M ²	Making the opening in brick masonry (careful demolition) including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge. (For door/ window/ventilators/exhaust fans)		1M ²	
3	37.00	Nos	Labour charges for removing the existing wooden doors, cupboards,UnderneathCupboard and Hanging cupboards (frame with shutters) complete set without any damage incl. available fittings and the re-fixing items to be stored in contractor's safe custody ,remaining handed over to depl.store/disposal as directed.		1No	
4	20.00	M ²	Labour charges for dismantling precast concrete slab /granaite top slab any size of thickness including clearing the debris away form site as directed.		1M ²	
5	11.00	M ²	Labour charges for removing the existing wooden/mdf/ply wood boardings from Working Table top,wherever necessary etc., including stacking within 50 metres lead. complete set without any damage including all available fittings and the usable items to be handed over to depl.store and the un-usable items handed over to disposal as directed.		1M ²	
6	150.00	RM	Labour charges for removing the existing GI/PVC pipes upto 75mm dia including all available specials, without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed.The rate inclusive of required lead and lift charges .		1RM	
7	100.00	RM	Labour charges for removing the existing GI/PVC pipes above 75mm dia including all available specials , without causing any damage. The serviceable materials shall be handed over to the departmental store, and the unserviceable items shall be disposed of as directed.The rate inclusive of required lead and lift charges .		1RM	
8	1.00	No	Labour charges for removing the existing bed pan sink with flush tank and all available fittings complete set without any damage and the same to be handed over to disposal, clearing the debris away from sites as directed.		1No	
9	26.00	Nos	Labour charges for removing the existing wash basin/SS sink /porcelin sink with all available fittings complete set without any damage and the same to be handed over to disposal, clearing the debris away from site as directed.		1No	
10	20.00	Nos	Labour charges for removing the existing EWC with flush tank complete set including all available fittings and specials, clearing the debris away from site as directed.		1No	
11	50.00	Nos	Labour charges for removing the existing brass/CP/PVC taps without any damage and the same to be handed over to disposal as directed.		1No	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
12	50.00	Nos	Labour charges for removing the existing wheel valve/Gate valve/ open stop cock etc. with all available specials without any damage and the same to be handed over to disposal as directed.		1No	
13	50.00	Nos	Labour charges for removing the existing towel rod/ towel rings/mirrors/paper trays/grab rail /shower rose/soap holders/cloth hoders/urinal pan with stand or any other usable accessories complete set without any damage including all available fittings and the re-fixing items to be stored in contractor's safe custody ,remaining handed over to deptl.store/disposal as directed.		1No	
14	405.00	RM	Labour charges for removing the existing MS/SS curtain rods/pelmets & corner guards without any damage incl. available fittings and the re-fixing items to be stored in contractor's safe custody ,remaining handed over to deptl.store/disposal as directed.		1RM	
15	380.00	M ²	Labour charges for chipping and removing the ceramic/ glazed tiles & Grainte floor set in CM from existing walls, floor and Table Top including base plastering completely without affecting the adjacent structures if any and clearing the debris away from site as directed.		1M ²	
16	100.00	M ²	Labour charges for chipping and removing the existing cement plastering from wall surface and wherever necessary and clearing the debris away from site as directed.		1M ²	
17	33.00	M ³	Labour charges for demolition of brick jelly lime concrete from existing toilet bay filling completely including clearing the debris away from site as directed.		1M ³	
18	3.00	M ³	Labour charges for demolition of Cement Concrete manually/ by mechanical means from existing Toilet flooring ,bed blocks and wherever necessary . completely including clearing the debris away from site within 50 metres lead as directed.		1M ³	
19	0.50	M ³	Labour charges for demolition of existing RCC works and including cutting of all reinforcement bars completely by manually/ mechanical means without affecting the adjacent structure including stacking of steel bars & clearing the debris away from site, as directed.		1M ³	
20	53.00	M ³	Labour charges for Chipping / removing the existing grano floor completely without affecting the adjacent area including clearing the debris away from site as directed.		1M ³	
21	1.00	M ³	Plain cement concrete 1:2:4 using 20mm size HBG machine broken jelly, M- sand including cost of all materials, mixing in mixer machine, laying, consolidation, self finishing and curing etc. complete for bed blocks and wherever necessary .		1M ³	
22			Supplying, fixing and removing of steel form work in line and level with materials as indicated for RCC elements at locations as stated, including all props, struts, sealing all joints between sheets to prevent leakage of slurry, treating the surface with approved oils and removing the formwork.			
a	23.00	M ²	for Cast-in-situ Table top		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
b	1.00	M ²	for Cast-in-situ lintels		1M ²	
23			Reinforced cement concrete M20 of design mix (to be approved by the dept.) or nominal volumetric mix of 1:1.50:3.00 using 20mm down graded HBG machine broken jelly free from flakes and M-Sand incl. mixing in mixer machine, laying, consolidation using vibrator, cost of all materials, curing etc. complete but excl. cost of steel reinforcement and form work.			
a	1.00	M ³	for Cast-in-situ Table top		1M ³	
b	0.10	M ³	for Cast-in-situ lintels		1M ³	
24	0.45	M ³	Casting and fixing in position of RCC 1:2:4 for precast lintel using 20mm size HBG machine broken jelly, M-sand incl. mixing, laying, consolidation, curing, cost of all materials, necessary mould and platform etc. complete but excl. cost of steel and fabrication.		1M ³	
25	0.50	M ³	Casting and fixing in position of RCC 1:2:4 for precast slabs using 3 to 8mm size HBG machine broken chips, M- sand including cost of all materials, necessary mould and platform, smooth finishing with CM 1:3 for all exposed surfaces and curing etc. complete but excluding cost of steel and fabrication		1M ³	
26	240.00	Kgs	Supplying fabricating,placing and tying in position of steel reinforcement including cost of 18 gauge MS binding wire etc.complete for all RCC works.		1Kg	
27	0.25	M ³	Brick wall in Cement-mortar 1:6 ,230mm and above thick using country bricks of size 230x100x70mm (kiln burnt) including cost all materials and curing etc., complete for existing opening closing , Steps ,ramps and wherever necessary.		1M ³	
28	8.00	M ²	Brick work in CM 1:4 for partition wall using country bricks of size 230x100x70mm (kiln burnt) including cost of all materials, labour for placing 2nos - 6mm dia MS rods at every 3rd course and curing etc. complete (steel will be measured separately)		1M ²	
29	58.00	M ²	Brick on edge work in CM 1:4 using country bricks of size 230x100x70mm (kiln burnt) including cost of all materials and curing etc. complete for cupboard, worktable support walls and wherever necessary.		1M ²	
30	115.00	M ²	Plastering with CM 1:5 , 12mm thick over new surface of internal Brick walls including cost of all materials and curing etc. complete.		1M ²	
31	10.00	M ²	Plastering with CM 1:5 , 20mm thick over external surface of new Brick walls including cost of all materials and curing etc. complete .		1M ²	
32	370.00	M ²	Base Plastering with CM 1:5 , 20mm thick over chipped surface of existing brick walls including cost of all materials and curing etc. complete.		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
33	75.00	Nos	Drilling & fixing of Nozzle: Identify the point to be grouted and care to be taken to drill at the horizontal and vertical joint along the other weak points. Drill holes of 19mm dia holes to depth of about 75mm. Fix the pvc nipple using rapid setting compound like Rendroc Plug of Fosroc or equivalent. Allow it to set complete		1No	
34	75.00	litres	Injection of Microfine cement: Prepare the micro fine cement slurry by adding the micro fine cement with water with minimum of 0.5 water cement ratio. Mixing to be done mechanically and expandable grout additive like Cebex 100 of Fosroc or equivalent at 225 gms per bag of cement need to be added to compensate the shrinkage. Inject the same using a positive displacement pump until the nipple refuses the grout or the grout comes out in the near by points. Cut the nipple and finish the same using polymer modified mortar - complete.		1litre	
35	155.00	M ²	Toilet Water proofing : Supplying and applying toilet and skirting water proofing treatment by using hydro carbon free liquid applied elastomeric water proofing membrane like brush bond type of (a)Fosarc-Nitoproof -600PF having 2 coats of minimum wet film thickness of each coat 1.50mm including filling of cracks in floor/wall,grouting the junction of wall and floor,making grooves for inserting water proof membrane etc.,complete as per manufacturer's instructions and technical data sheet.(b)Supplying and fixing in position of toilet floor and skirting with single layer of white colour plain 45GSM filler glass mesh for proper water proofing of approved sample shall be provided before applying protective first coat and second coat of plastering including cost of all materials,properly stretched and nailed,ensuring equal thickness of plaster on both floor and walls sides of mesh.(c)Applying protective coats of plastering with 2 coats consist of base and top plastering with 1:3,8mm thick and 12mm thick respectively in 2 successive layers etc.,complete.Incl.cost for Surface preparation, wastage, curing,etc, measurement shall be on the basis of net area water proofed.include drying and cleaning the surface free of dust, proper water ponding test,leakage points if any found with PU grout etc.The actual area treated shall be measured and paid.No extra shall be paid for any fillets,grooves or rounding.The contractor shall provide a performance guarantee for five-5 years on stamp paper in an approved form.		1M ²	
36	33.00	M ³	Cement concrete 1:4:8 using 20mm size brick jelly for toilet filling to a required height incl. cost of all materials, mixing , laying, consolidation and curing etc. complete.		1M ³	
37	3.00	M ³	Encasing with cement concrete 1:3:6, using machine broken HBG chips 10 to 12mm size to PVC pipes in toilet pits, and wherever necessary incl. cost of all materials, necessary shuttering, laying, consolidation and curing etc. complete.		1M ³	
38	100.00	M ²	Supplying and laying of Non-skid Vitrified/Ceramic plain tiles, 1st quality 300X300mm size of approved make and colour set in CM 1:3, base with 2mm spacers in both direction including grouting the joints with epoxy grout of approved make and matching colour, giving proper slope, cleaning and curing etc. complete for toilet floor & sluice floor .(Basic rate of tile Rs.600.00 / 1M²-Excl.GST-18%)		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
39	280.00	M ²	Supplying and fixing of Glazed Plain wall tiles 1st quality 300x300mm/ 300x450mm mm size of approved make and colour set in CM 1:3 base including pointing with white cement mixed with colour pigments, providing best quality PVC corner edge beads, cleaning and curing etc. complete for dadoing.(Basic cost of tiles :- Rs.450.00/1M²-Excl.GST-18%)		1M ²	
40	20.00	M ²	Supplying and fixing in position of highly polished Granite slab 18 to 20mm thick of approved quality and approved sample, set in CM 1:3, including cost of all materials, pointing white cement with matching colour pigments, cleaning and curing etc. complete. For Table top & Floor strips.(Basic rate of granite Rs. 2,000.00 /1M²-Excl.GST-18%).		1M ²	
41	4.00	Nos	Extra for providing opening of required size & shape for wash basins/ kitchen sink in kitchen platform, vanity counters and similar location in marble/Granite/stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete.		1No	
42	29.00	RM	Providing full nosing to exposed edges of granite in table top etc. complete		1RM	
43	53.00	M ³	Screed concrete PCC 1:3:6 using 3to8mm size HBG machine broken chips,m-sand including cost of all materials ,mixing, laying,consolidation and curing etc., complete under floor wherever necessary to eliminate the undulations.		1M ³	
44	700.00	M ²	Supplying and fixing of Vitrified/ceramic tiles ,1st quality 600x600mm size of approved make and colour set in CM 1:3, base with 3mm spacers in both directions including pointing with Roffee compound tile mate /approved equivalent mixing with colour pigments,cost of all materials,cleaning and curing etc. complete for floor.(Basic rate tile-Rs.-600.00-/1M² Excl.GST-18%)		1M ²	
45	90.00	M ²	Supplying and fixing of Vitrified/ceramic tiles of size 450x450mm 100mm/150mm high 1st quality of approved make, pattern and colour set in CM 1:3 to match the joints of the floor including cutting to size,pointing with Roffee compound tile mate /approved equivalent mixing with colour pigments including cost of all material, cleaning and curing etc. complete.For Skirting. (Basic Rate of Tile Rs.-600.00 /1M² Excl.GST-18%)		1M ²	
46	700.00	M ²	Providing and applying Water proofing treatment to the slabs at all locations with 2 coats water based Bituminous liquid membrane Tarfelt LM, 1mm thick, with 2 coats one after the other dries. The direction of the coatings will be right to left vice versa.Tarfelt LM(STP) 50:50 water mixing, including surface preparation,leakage checking,curing , and providing coving with cement mortar as per site condition and manufacturer standard specification.		1M ²	
47	5.00	M ²	Grano floor finishing with CC 1:1.5:3 to a average thickness of 25mm using M-Sand and 3mm to 8mm size HBG machine broken chips including cost of all materials, laying, consolidation, thread lining if necessary, neat finishing and curing etc. complete		1M ²	
48			Supplying and fixing in position of following Wooden doors frame with shutters including cost of all materials, furniture fittings etc complete as per Sketch and Specifications.			

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
a	2.52	M ²	D-1200X2100MM		1M ²	
b	1.89	M ²	D1-900X2100MM		1M ²	
c	39.73	M ²	D2-860X2100MM		1M ²	
49			Supplying and fixing in position of following Cupboards and underneath cupboards frame with shutter including cost of all furniture fittings etc complete as per Sketch and Specifications.			
a	5.04	M ²	CB1-1200x2100MM		1M ²	
b	3.15	M ²	CB2-750x2100MM		1M ²	
c	24.50	M ²	CB-900x2100MM		1M ²	
d	13.80	M ²	UCB-1050x900MM		1M ²	
50	20.00	Nos	Supplying, transporting to Site , Unloading , Safe storage, installing, testing and commissioning of White colour EWC with "S/P " trap parryware make with plastic seat cover (Heavy duty type) , pan connector etc.complete. Cost including conveyance of all materials to the site, all labour charges etc., complete in all floors including cutting and making rough finishing the walls and floors wherever required,checked and directed by the Engineer-in-charge.		1No	
51	1.00	No	Supplying and making of Bed Pan stainless steel sink using 304 grade 16G stainless steel sink, 100mm dia S.S. pipe 18G with flange and fabricated 14G stainless steel 'P' trap with flange including cost of all materials (excluding cost of flush tank) 1/2" S.S. pipe (304 grade 16G) at around sink inner for flushing, bolts and nuts, necessary washer for connecting S.S. "P" trap and S.S. sink etc., Complete.		1No	
52	21.00	Nos	Supplying and fixing in position of Slimeline combiflush twin flush type plastic cistern (white) complete set for EWC / Bed Pan sink including required fittings such as 1st quality inlet nylon connection,pvc flushing pipe etc., complete.		1No	
53	1.00	No	Supplying and fabricating stainless steel Deep sink using 16 Gauge 304 grade sheet of approved quality ,including the cost of all materials,fabrication charges,cutting,bending to required size and shape,welding,grinding,buffering, polishing to glossy finish providing drain holes to fix the waste coupling,finishing in all respects,etc.,complete. Size : 1.20x0.60x0.50m		1No	
54	23.00	Nos	Supplying, transporting to Site , Unloading , Safe storage, installing, testing and commissioning of Parryware White glazed wash hand basin 550x400mm including all fittings such as SS pipe brackets/S.S Rag bolts set , 15mm dia CP pillar cock (plumber make),1st quality inlet nylon connection,CP waste coupling, PVC waste pipe etc., complete. Cost including conveyance of all materials to the site, all labour charges etc., complete.		1No	
55	3.00	Nos	Supplying and fixing in position of approved make of Porcelain sink (White) 600x450x250 mm size including cost of all fittings such as CP waste coupling,waste hose etc., complete. (Hindware or approved equivalent)		1No	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
56			Supplying and fixing in position of following types of plumbing fittings of approved make including cost of all materials and required specials etc., complete.			
a	44.00	Nos	15mm dia CP Angle cock for Whb & Flush tank		1No	
b	20.00	Nos	15mm dia CP Two way bib cock with health faucet		1No	
c	26.00	Nos	CP Bottle trap		1No	
d	4.00	Nos	15mm dia CP long body bib cock		1No	
e	26.00	Nos	15mm dia CP short body bib cock		1No	
f	2.00	Nos	15mm dia CP Open stop cock.		1No	
g	19.00	Nos	15mm-PVC-shower rose		1No	
57	3.00	Nos	Supplying and fixing in position of 15mm dia CP brass Elbow operated clinical Bib cock with Wall Flange including cost of all material and required specials etc., complete. (Vijay (Model No: 1054) / Peaco make or approved equalent)		1No	
58	6.00	Nos	Supplying and fixing of Supreme make PVC nahini plain floor trap of 110mm dia. with S.S round jally including cost of cement solvent for joining,cement mortar for fixing in position etc., complete.		1No	
59	20.00	Nos	Supplying and fixing of 110mm dia Supreme make PVC multi floor trap with S.S. hinged type square of cement solvent for joining,cement mortar for fixing in position etc., complete.		1No	
60	26.00	Nos	Supplying and Fixing in position of Chromium plated towel rod 600mm long with required teak wood plugs and screws including cost of all material etc., complete.		1No	
61	4.00	Nos	Supplying and fixing in position of aluminium powder coated 150mm size towel ring with required teak wood plugs and brass screws including cost of all material etc., complete.		1No	
62	22.00	Nos	Supplying and fixing in position of mirror of size of 600 x 450 mm with hard board back & plastic frame around including cost of all materials and required screws etc. complete.		1No	
63	52.00	Nos	Supplying and fixing in position of stainless steel pipe grab rail 25mm dia 18 gauge, 304 grade including cost of all materials, bending to required shape fixing, grouting with CM finishing in all respects etc. complete(total length 0.760m).		1No	
64	2.00	Nos	Supplying and fixing in position of Foldable stainless steel grab bar of Polo / Approved make PVC coated 600mm long incl cost of all screws ,materials etc complete as per the direction of the Engineer in charge...		1No	
65	25.00	Nos	Supplying and fixing in position of Chromium plated soap tray with required teak wood plugs and brass screws including cost of all material etc., complete.		1No	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
66			Supplying and fixing of the following PVC pipes including cutting charges, cost of cement solvent for joining and fixing with necessary specials, cost of all materials and specials etc., complete for internal pipe lines. (ABOVE GROUND LEVEL)			
a	15.00	RM	40mm dia 6Kgs/CM ² (incl. specials)		1RM	
b	25.00	RM	50mm dia 6Kgs/CM ² (incl. specials)		1RM	
c	15.00	RM	63mm dia 4Kgs/CM ² (incl. specials)		1RM	
d	30.00	RM	75mm dia 4Kgs/CM ² (incl. specials)		1RM	
e	30.00	RM	110mm dia 4Kgs/CM ² (incl. specials)		1RM	
67			Supply and Installing at site PVC SWR Pasted pipe using Solvent Cement ISI Marked [As per IS 13592] with PVC special fittings , Plain Bends, Door bends, Couplers, Reducers, Single Tees, Door Tees, Double Tees, Reducing Tees, Plain Ys, Door Ys, Double Ys, Elbows , Door Elbows etc. Adapters, Air vents, Clamping with GI U Clamps as required for firmly installing the pipes. Testing of the system for leakage and Air tightness (Make: Ashirwad,Supreme, Finolex or approved equalent) excluding cost of MS brackets which will be paid seperately.			
a	40.00	RM	75mm dia - Type-B (incl. specials)		1RM	
b	40.00	RM	110 mm dia - Type-B (incl. specials)		1RM	
68	50.00	Kgs	Supplying and fixing of required size brackets and clamps using MS Angles, MS flats, and MS threaded rods for plumbing instructed by Engineer including one coat zinc chromate primer, two coats with synthetic enamel paint making holes in wall for fixing cement concrete for packing finishing the surfaces etc., complete		1Kg	
69			Supplying of G.I special clamp with coach screw, U bolt , nut & washer of the following sizes of G.I Pipe supports and specifications etc. complete.			
a	10.00	Nos	100 mm length		1No	
b	10.00	Nos	230 mm length		1No	
70			Supplying , cutting,threading, laying and joining of G.I. pipes ' B ' class ISI make with necessary ' UNIK' make specials including cost of all required materials, clamps, teak wood plugs and screws etc., complete. (ABOVE GROUND LEVEL)			
a	20.00	RM	15mm dia		1RM	
b	40.00	RM	20mm dia		1RM	
c	40.00	RM	25mm dia		1RM	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A			CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)			
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
d	30.00	RM	32mm dia		1RM	
e	30.00	RM	40mm dia		1RM	
71			Supplying and fixing in position of ISI Elco brand gun metal Gate valve heavy duty including cost of all materials and required specials etc., complete.			
a	10.00	Nos	15mm dia		1No	
b	10.00	Nos	20mm dia		1No	
c	10.00	Nos	25mm dia		1No	
d	1.00	No	32mm dia		1No	
e	1.00	No	40mm dia		1No	
f	1.00	No	65mm dia		1No	
72			CPVC SDR 11 Piping System (water supply:Domestic water,flushing piping system) : Supply and Installing at site exposed on wall side- CPVC SDR 11 ASTM D 2846 Pipes (Equivalent Standard Size) with suitable CPVC Schedule 80 fittings (Ts, Elbows, Bends, Reducers, Couplers, Ys etc.) Adapters, Clamping with GI U Clamps,teak wood plugs and screws as required for firmly installing the pipes, having thermal stability for Hot and Cold Water supply. Joined using Solvent Cement fittings with metal inserts (brass lined specials at outlet points) suitable for the working pressure.Hydrostatic testing of the Pipes using necessary test pressure for specified time period etc. (Make: Ashirwad, Supreme / Ajay / Astral or approved equivalent)			
a	10.00	RM	15mm dia		1RM	
b	40.00	RM	20mm dia		1RM	
c	10.00	RM	25mm dia		1RM	
73	1,480.00	M ²	Scraping completely and cleaning the white (or) colour washed surface (or) snowcem of old walls and ceilings using by machine or maual using putty plate, sand paper and wire brush including scaffolding and clearing the debris away from site etc ,complete.		1M ²	
74	590.00	M ²	Painting two coats using Acrylic emulsion paint approved make and colour over old painted surfaces of walls & ceilings incl.surface preparation , necessary touch up putty , brush, cost of all materials & scaffolding etc. complete.		1M ²	
75	880.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over old / new walls and ceiling with one coat of water based cement primer after preparation of the surface smooth and even with Birla wall care putty / approved equivalent including cost of all materials, proper roller finish, brush and scaffolding etc. complete.		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
Sl.No.	Quantity		Description of the work	Rate	Unit	Amount
76	570.00	M ²	Painting two coats using synthetic enamel paint of approved make & colour over the old painted surface of walls & ceilings incl. Surface preparation, cost of all materials, necessary touch up putty , brush & scaffolding etc. complete .		1M ²	
77	850.00	M ²	Painting two coats with synthetic enamel paint of approved make colour over old / new walls with one coat of oil based primer after preparation of the surface smooth and even with Birla wall care putty / approved Equivalent including cost of all materials, brush and scaffolding etc. complete.		1M ²	
78	160.00	M ²	Painting two coats using washable oil bound Distemper of approved make and colour over old surface of walls & ceilings incl. surface preparation with necessary touch up putty , cost of all materials,brush and scaffolding etc, complete.		1M ²	
79	640.00	M ²	Painting two coats with washable oil bound distemper of approved make and colour over old/new walls and ceilings with one coat of water based cement primer after preparation of the surface smooth and even with Birla wall care putty / approved equivalent incl. cost of all materials, scaffolding and brush etc. complete.		1M ²	
80	10.00	M ²	Providing and applying two coats of White Cement Washing using Birla/Ramco White Cement or approved equivalent over new/old surface of walls and ceilings incl. cost of all materials, brush, scaffolding and curing etc. complete. The surface should be thoroughly cleaned, all cracks filled up with white cement paste and wetted before painting and curing should be done as per instructions of engineer.		1M ²	
81	10.00	M ²	Painting two coats with Anti fungal paint of approved make and colour over old/new walls and ceilings with one coat of penetrating primer after preparation of the surface smooth and even with Birla wall care putty approved equivalent including cost of all materials, brush and scaffolding etc. Complete as per manufacturer's standard specifications.		1M ²	
82	185.00	M ²	Painting two coats using synthetic enamel of approved make & colour over the old woodwork incl. painting the furniture fittings where required, surface preparation with application of putty, cost of all materials, brush and scaffolding etc. complete.		1M ²	
83	105.00	M ²	Painting two coats with synthetic enamel paint of approved make and colour over new wood works with one coat of wood primer incl, painting the furniture fittings where required, surface preparation with application of putty, cost of all materials brush and scaffolding etc complete.		1M ²	
84	125.00	M ²	French polishing to a satisfactory finish over old wood work incl, surface preparation cost of all materials, etc. completeFor Door / window, wooden hand rail, cupboard fully wood, cupboard with MDF laminated board etc. complete .		1M ²	
85	50.00	M ²	Painting two coats using synthetic enamel paint of approved make & colour over the old / new ironwork incl. surface preparation, necessary putty, cost of all materials, brush and scaffolding etc. complete.		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
86			Painting two coats with synthetic enamel paint of approved make and colour over new GI pipes with one coat of zinc chromate including cleaning the pipes, cost of all materials, brush, scaffolding etc. complete.			
a	20.00	RM	15mm dia		1RM	
b	40.00	RM	20mm dia		1RM	
c	40.00	RM	25mm dia		1RM	
d	30.00	RM	32mm dia		1RM	
e	30.00	RM	40mm dia		1RM	
87	84.00	RM	Providing and fixing of fastrack I.V .Track- hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon hooks,necessary screws for track system and cost of all materials,cost of labour and transportation,etc		1RM	
88	32.00	Nos	Providing and fixing of fastrack I.V . stand- hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon hooks,necessary screws for track system and cost of all materials,cost of labour and transportation,etc		1No	
89	158.00	RM	Providing and fixing of fastrack Curtain Track hospital cubical system comprising aluminium powder coated track of approved colour with necessary nylon hooks,necessary screws for track system and cost of all materials,cost of labour and transportation,etc.complete.		1RM	
90	141.00	RM	Supplying and fixing in position of 25mm dia (OD) MS powder coated curtain rod 20 gauge of approved make and colour including cost of all materials,cutting to required size ,fixing and finishing in all respects etc., as directed by the Engineer-in-charge.		1RM	
91	166.00	Nos	Supplying and fixing in position of MS powder coated curtain end brackets of approved model and colour with necessary wooden plugs/ supports ,screws including cost of all materials etc., as directed by the Engineer-in-charge.		1No	
92	19.00	RM	Supplying and fixing in position of edge protection angle using Aluminium angle 40x25x3mm in toilet/sluice area (or) other areas wherever required in the level difference found in floor level etc,complete.		1RM	
93	30.00	RM	Towards the labour charges for re-fixing in position of existing SS corner guards completely including straightening , cleaning, buffing, polishing,welding and jointing if any required,making them in usable condition ,fixing and finishing in all respects as directed by the Engineer-in-charge. (Required corner guards/wall guards will be supplied by the department at free of cost)		1RM	
94	22.00	M ²	Supplying and fixing in position of wall cladding work using polished stainless steel sheet 18 gauge SS 304 grade ,300mm height with back 18mm plywood incl. cost of all materials teak wood plug, screws & nails etc complete as per Engineers instructions .		1M ²	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
95	10.00	Nos	Supplying and fixing in position of stainless steel angle 50x50mm - 304 grade 20 gauge corner guard 1500mm-height wherever necessary including cost of all materials cutting,bending ,drilling holes, screws and nails etc. complete.		1No	
96	5.00	Nos	Labour charges for fixing the existing doors,windows, ventilators ,underneath/Hanging Cupboards (frame with shutters) complete set including all available fittings as directed. (Required doors,windows, ventilators, underneath/Hanging Cupboards will be supplied by the department at free of cost)		1No	
97	5.00	Nos	Providing minor repair charges to the existing doors, windows & ventilators including replacement of existing damaged furniture fittings with new one including charges for removing and refixing,making them to functional condition , fixing and finishing in all respects as directed by the engineer-in-charge. (required furniture fittings , wooden scantlings and teak wood beadings will be supplied by dept.at free of cost & it is applicable for all available sizes as per site condition, which requires minor repairs only)		1No	
98	5.00	Nos	Towards the Labour charges for engaging Helpers for intercarting the department office furnitures stored at identified locations so as to provide access and clearance for work front and cleaning the tables prior to handing over the user department as per the direction of the Engineer in charge.		1No	
99	2.00	Nos	Supplying and fixing in position of Hydraulic door closer (Rolex Make) to wooden/aluminium doors complete set including required screws and nails etc., complete.		1No	
100			Supplying and fixing in position of following size of plywoods covering /closings to existing openings (or) match the difference level of wall thickness with necessary screws, nails & accessories etc., complete. (For Openings /windows /ventilators and AC indoor unit)			
a	0.50	M ²	12mm thick plywood		1M ²	
b	0.50	M ²	18mm thick plywood		1M ²	
101			Making through holes in Plain or Reinforced Cement Concrete /Brickwork with Diamond Core Drilling System by using BOSCH power tools of following diameter.			
a	20.00	Nos	upto 200mm (Plain or Reinforced Cement Concrete) thickness upto 250mm		1No	
b	20.00	Nos	upto 200mm (Brickwork) thickness upto 250mm		1No	
102	20.00	Nos	Bore Packing around the pipes in Brick walls and Concrete members applying bonding agent of SBR Latex or approved equivalent around the internal partition of surface, Quick setting component of Rendroc plug/approved equivalent packed externally and the gaps around the pipe tightly packed with GP2 Chemical. Provide the backer rods if the gap around the pipe have more than 25mm including cost of all materials, labour charges, neat finishing, curing, etc., complete. (Note : Water to be stagnated around the bore packing about 48 hours and water leakage has to be cleared from Engineer in charge.)		1No	

NAME OF THE WORK:PROPOSED MODIFICATION OF "O4" WARD AT FOURTH FLOOR OF "O" BLOCK-EAST IN CMC, TOWN CAMPUS.						
SCHEDULE-A		CIVIL WORKS- (DEMOLITION WORK+PROPOSED WORK)				
SI.No.	Quantity		Description of the work	Rate	Unit	Amount
103	10.00	Nos	Providing and fixing 16 mm M.S. Fan clamps of standard shape and size in existing R.C.C. slab, including cutting chase, anchoring clamp to reinforcement bar, including cleaning, refilling, making good the chase with matching concrete, plastering and painting the exposed portion of the clamps complete. (Required MS Clamps will be supplied by the department at free of cost)		1No	
104	1,910.00	Kgs	Providing fabricating, erecting in position of MS Structural steel at all levels, locations, leads & lift for SHS,ISA,ISMC,chequered plate ,anchor foundation bolt,M.S.base plate ,bolts and nuts ,M.S.pipes etc. including making of necessary templates as directed, cutting, drilling, welding, grinding, temporary supports at all locations where required including preparing the surface by sanding down thoroughly, grinding smooth all weld-burrs and filling with metal paste where ever required and painting with 1 coat of anti-corrosive zinc chromate primer and two coat of synthetic enamel paint of approved make and colour etc complete For MS walkway platform to access AC out door units. (Details as per sketch and specification)		1Kg	
105	20.00	Nos	Providing and drilling suitable holes in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 160mm in RCC column/slab/beam including fixing in position of M16- HIT-V-5.8 Anchor rod of 260mm long with Anchorage depth 160mm Hilty bolt with Hilti Chemical Grout /approved equivalent Externally threaded-hammer drilling as per standard manufacturer specification and as per the direction of the Engineer in-charge.(Details as per sketch and specification)		1No	
106	30.00	Lorry loads	Transporting the debris by lorry from CMC Town campus to outside of the campus including loading and unloading charges etc. complete.(capacity 5.50 M ³ /load)		1 Lorry load	
				Sub Total		
(Excl. GST) C/o to CONSOLIDATED SUMMARY						