

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
1	10.00	M ³	Labour charges for Demolishing of existintg brick walls in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		1M ³	
2	3.00	Nos	Labour charges for removing the existing Steel/ Aluminium doors & windows (frame with shutters) complete set without any damage including all available fittings as directed.		1No	
3	50.00	M	Labour charges for removing Pipelines upto 75mm dia./G.I./ PVC/C.I. with all available specials without any damage including lead and lift , clearing the debris away from site as directed. (If any routed below the paver block area, necessiated to remove or re-route)		1RM	
4	25.00	M	Labour charges for removing the existing GI/PVC/C.I. pipes above 75mm dia upto 150mm dia without any damage including lead and lift charges , clearing the debris away from site as directed. (If any routed below the paver block area, necessiated to remove or re-route)		1RM	
5			Labour charges for removing the following dia existing wheel valve/Gate valve/ open stop cock etc. with all available specials without any damage as directed.			
a	2.00	Nos	15mm dia to 25mm dia		1No	
b	2.00	Nos	32mm dia to 65mm dia		1No	
6	20.00	M ²	Labour charges for dismantling of existing damaged precast slab thickness above 40mm up to 75mm from cable trench or wherever necessary including clearing the debris away from site as directed.		1M ²	
7	5.00	Nos	Labour charges for removing the existing brass/CP tap without any damage as directed.		1No	
8	2.00	M ³	Labour charges for Chipping / removing the existing grano flooring without affecting the adjacent area including clearing the debris away from site as directed.		1M ³	
9	5.00	M ²	Labour charges for chipping and removing the ceramic/ glazed tiles, Kotah & Grainte in CM from existing walls, floor and Table Top including base plastering and clearing the debris away from site as directed.		1M ²	
10	3.00	M ³	Labour charges for demolition of Plain Cement Concrete manually/ by mechanical means from existing foundation and flooring completely including clearing the debris away from site within 50 metres lead as directed, neat finishing etc., Complete.		1M ³	
11	1.00	M ³	Labour charges for demolition of reinforced cement concrete including cutting reinforcement bars manually/ by mechanical means including stacking of steel bars without affecting the adjacent structure incl. clearing the debris away from site, as directed.		1M ³	
12	40.00	M ²	Labour charges removing the existing GI roof sheet without any damage including clearing the debris away from site as directed.		1M ²	
13	650.00	Kgs	Labour charges for dismantling of existing trusses, purlins and rafters above 10 metres span and 5 metres height including clearing away from site and stacking as directed. (Truss, purlin & MS Handrails)		1Kg	
14	3.00	Nos	Labour charge for Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :For pipes 100 to 250 mm diameter		1No	
15	35.00	M ²	Labour charges for dismantling aluminium / wooden partitions, doors, & fixed glazing including clearing the debris away from site as directed.		1M ²	
16	20.00	M ²	Labour charges for dismantling Gypsum/ Bison/ Cement/ wooden partitions, wall panelling including clearing the debris away from site as directed.		1M ²	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
17	25.00	M	Labour charger of Taking out existing kerb stones of all types from footpath/central verge , including removal of mortar etc., stacking of serviceable material and clearing the debris away from site as directed		1RM	
18	5.00	Nos	Labour charges for dismantling fencing R.C.C./Steel post at the point of projection above the concrete or ground including clearing the debris away from site as directed.		1No	
19	5.00	M ²	Labour charges for removing the existing GI/Plastic coated chainlink fencing completely without any damage as directed.		1M ²	
20	2.00	Nos	Dismantling of manhole including R.C.C. top slab, C.I. cover with frame , including stacking of useful materials near the site and disposal of unserviceable materials within 50 m lead as per direction of Engineer-in-charge: Rectangular manhole 120x90 cm and beyond 90 cm depth		1No	
21	100.00	M ²	Labour charges for removing the existing paver block completely without any damage (Excluding sand cushion the same will be retained) including shifting the good conditioned and re-usable condition paver blocks to be stocked in an identified location ,the remaining damaged items to be disposed off & clearing away from site as directed.		1M ²	
22	5.00	M ³	Labour charges for removal of excess sand cushion below the paver blocks wherever necessary as per required profile of paver including shifting and stocking the useable condition sand in an identified location remaining unused to be disposed off and clearing the same away from site as directed.		1M ³	
23	10.00	M ²	Dismantling wooden boardings in lining of walls, partitions, Working Table top.,etc., including stacking within 50 metres lead		1M ²	
24			Earth work excavation for foundation and trenches in all kind of soil upto required depth incl. refilling the sides of foundation with selected excavated earth, watering, ramming and consolidation etc. complete.			
a	5.00	M ³	-do- upto a depth of 1.50m		1M ³	
25	5.00	M ²	Earth work for large open area excavation in all kinds of soil (average depth of 300mm) including side cutting, sectioning and levelling around the building wherever necessary so as to maintain the same level etc. complete		1M ²	
26	1.00	M ³	Labour charges for filling available excavated earth for basement in layers of required thick including watering, ramming and consolidation etc. complete.		1M ³	
27	2.00	M ³	Supplying and filling of M-Sand for foundation and basement in layers of required thick including watering, ramming and consolidation etc. complete.		1M ³	
28	1.00	M ³	Plain cement concrete 1:2:4 using 20mm size HBG machine broken jelly, coarse river sand including cost of all materials, mixing in mixer machine, laying, consolidation, self finishing and curing etc. complete under foundation/bed block		1M ³	
29	5.00	M ³	Plain Cement concrete 1:4:8 using 40mm size HBG machine broken jelly,M-Sand including mixing in mixer machine, laying, consolidation and curing etc.Complete for Flooring and wherever necessary.		1M ³	
30	10.00	M ²	Supplying, fixing and removing of 12mm thick waterproof plywood formwork in line and level with materials as indicated for RCC elements at locations as stated, including all props, struts, sealing all joints between sheets to prevent leakage of slurry, treating the surface with approved oils and removing the formwork. . The work shall be carried out as per the technical specifications given herewith. Note: total surface area in contact with concrete shall be measured		1M ²	
31			Reinforced cement concrete M20 of nominal volumetric mix of 1:1.50:3.00 using 20mm down graded HBG machine broken jelly free from flakes and M-sand incl. mixing in mixer machine, laying, consolidation using vibrator, cost of all materials, curing etc. complete but excl. cost of steel reinforcement and form work .			
a	1.00	M ³	For Plinth beam		1M ³	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
32	330.00	Kgs	Supplying fabricating,placing and tying in position of steel reinforcement including cost of 18 gauge MS binding wire etc.complete for all RCC works.		1Kg	
33	0.10	M ³	Casting and fixing in position of RCC 1:2:4 for precast slabs using 3 to 8mm size HBG machine broken chips, coarse sand including cost of all materials, necessary mould and platform, smooth finishing with CM 1:3 for all exposed surfaces and curing etc. complete but excluding cost of steel and fabrication.		1M ³	
34			Brick wall in Cement-mortar 1:6,230mm and above thick using non-metric bricks of size 230x115x75mm (chamber burnt) including cost all materials and curing etc., complete.			
a	2.00	M ³	Foundation and basement.		1M ³	
b	0.50	M ³	super structure up to floor v level		1M ³	
35	50.00	M ²	Brick work in CM 1:4 for partition wall using non-metric bricks of size 230x115x75mm(chamber burnt) including cost of all materials, labour for placing 2nos - 6mm dia MS rods at every 3rd course and curing etc. complete (steel will be measured separately & Supplied by Dept free of cost.).		1M ²	
36	10.00	M ²	Brick on edge work in CM 1:4 using non-metric bricks of size 230x115x75mm(chamber burnt) including cost of all materials and curing etc. complete for cupboard,working platform support walls.		1M ²	
37	60.00	M ²	Plastering with CM 1:5, 12mm thick over new surface of internal brick walls including cost of all materials and curing etc. complete.		1M ²	
38	10.00	M ²	Plastering with CM 1:3, 20mm thick mixed with approved quality water proof compound 2% by weight of cement used for damp proof course including cost of all materials, finishing and curing etc. complete.		1M ²	
39	65.00	M ²	Plastering with CM 1:5, 20mm thick over external surface of new brick walls including providing grooves as required, cost of all materials and curing etc. complete in all floors at all heights.		1M ²	
40	0.50	M ³	Encasing with cement concrete 1:3:6 , using machine broken HBG chips 10 to 12mm size to PVC pipes in toilet pits and wherever necessary incl. cost of all materials, necessary shuttering, laying, consolidation and curing etc. complete.		1M ³	
41	5.00	M ²	Supplying and laying of Non skid vitrified/ceramic plain tiles, 1st quality 300x300mm size of approved make and colour set in CM 1:3 , base with 2mm spacers in both direction including grouting the joints Cementitious grout to matching colour, giving proper slope, cleaning and curing etc. complete for toilet floor (Basic rate of tile Rs. 600.00 /M², -Excl.GST)		1M ²	
42	15.00	M ²	Supplying and fixing of Glazed Plain wall tiles 1st quality 300x450mm/300x600mm size of approved make and colour set in CM 1:3 base including pointing with white cement mixed with colour pigments, providing best quality PVC corner edge beads, cleaning and curing etc. complete for dadoing. (Basic cost of tiles :- Rs.450.00/1M² Excl.GST)		1M ²	
43	6.00	M ²	Grano floor finishing with CC 1:1.50:3 using sand and 3mm to 8mm size HBG machine broken chips including cost of all materials, laying, consolidation, thread lining if necessary, neat finishing and curing etc. complete. 40mm average thick.		1M ²	
44	10.00	M ²	Supplying and laying of Kotah stone 18 to 20mm thick of approved quality and size set in CM 1:3 base, including cost of all materials, pointing white cement with matching colour pigments,providing bevelled nosing , polishing with tin oxide to high degree glossy finish, cleaning and curing etc. complete For Flooring. (Basic cost of kotah stone:- Rs. 600.00 /1M² Excl.GST).		1M ²	
45	2.00	M ²	Supplying and fixing of Kotah stone 18 to 20mm thick of approved quality and size set in CM 1:3 base, including cost of all materials, pointing white cement with matching colour pigments, polishing with tin oxide to high degree glossy finish, cleaning and curing etc. complete for Staircase Risers/Skirting. (Basic cost of kotah stone:- Rs. 600.00 /1M²-Excl.GST).		1M ²	
46			Supplying and fixing in position of following types of Aluminium Sliding & Openable Doors frame with shutters & Aluminium Partition with Openable Door including cost of all materials,furniture fittings etc., complete as per sketch and specification.			

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
a	3.00	M ²	Door -SD-1200x2100mm		1M ²	
b	11.00	M ²	Alu. Partition with Openable door - AD		1M ²	
47	3.00	M ²	Providing of 35mm thick Factory made Pre-laminated ABS (Acrolonitrile Butadyne Styrene) Door shutter consisting of all round frame made out of water proof solid foam PVC bar of size 20x32mm, reinforced by 32x 32mm-2 Nos for vertical made out of LVL (Laminated Veneer Lumber), core material of 32 mm thick high density craft paper honey comb board, sandwiched on both sides with pre-laminated ABS sheet thickness of 1.50mm. PVC edge banding of size 0.45mm on the vertical sides. Hardware made out of steel coated butterfly hinges-3 Nos, 2 Nos Aluminium towerbolt ,cylinder lock,150mm long Aluminium-D-type Handle-2 Nos and using Silicone sealant to provide water tight seal between the doors and adjoining construction both inside and outside complete for finished item of work etc., complete complying with the standard specification. The door shutter and frame should be got approved from the Engineer-in-charge before use on work.(Size of door :1200X2100MM)		1M ²	
48			Supplying and fixing in position of following types of aluminium windows, (Openable frame with shutters) including cost of all materials,furniture fitting etc., complete as per sketch and specification			
a	2.00	M ²	Window -W-1200x1200mm		1M ²	
49			Supplying and fixing in position of Aluminium Ventilator where ever necessary as per sketch and specification.			
a	1.00	M ²	Ventilator -V-750x600mm		1M ²	
50			Supplying and fixing in position of following sizes of NCL single glass- 2/3&4 leaf openable shutters with windows , 2-panel fixed glass ventilators ,1-panel fixed galss ventilators,2-panel fixed mesh,1-panel fixed mesh ventilators and top hung ventilators including cost of all materials, furniture fittings etc complete as per NCL product standard Specifications. (Note:-Caulking shall be done using Silicone sealant to provide water tight seal between the windows and adjoining construction both inside and outside at free of cost.No separate payment shall be made for this.)			
a	QRO	M ²	Window -W-1200x1200mm		1M ²	
b	QRO	M ²	Ventilator -V-750x600mm		1M ²	
51	QRO	M ²	Supplying and fixing in position of MS grill with outer frame,approved design using 10mm MS square rod horizontally welded to 12x6mm Ms flats at 125mm Pitch powder coated to black colour including cost of all materials,fabrication charges complete as per NCL product standard Specifications. (for windows and ventilators)		1M ²	
52	300.00	Kgs	Supplying, fixing of M S Hand rail approved design using Ms flats,square rods, top MS Pipe including cost of all materials,fabrication charges,1 coat of yellow oxide primer and two coat of synthetic enamel paint etc etc., complete		1Kg	
53			Supplying and fixing of the following PVC pipes including cutting charges, cost of cement solvent for joining and fixing with necessary specials, cost of all materials etc., complete for internal pipe lines. (ABOVE GROUND LEVEL)			
a	5.00	M	40mm dia 6Kgs/CM ² (incl. specials)		1RM	
b	5.00	M	50mm dia 6Kgs/CM ² (incl. specials)		1RM	
c	1.00	M	63mm dia 4Kgs/CM ² (incl. specials)		1RM	
d	1.00	M	75mm dia 4Kgs/CM ² (incl.specials)		1RM	
e	1.00	M	110mm dia 4Kgs/CM ² (incl.specials)		1RM	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
54			Supplying and fixing of the following dia Supreme make SWR PVC Type-B pipes including cutting charges, cost of cement solvent for joining and fixing with necessary SWR PVC plumbing specials for external sewage line, waste water line including necessary scaffolding etc., complete but excluding cost of MS brackets which will be paid seperately.			
a	3.00	M	75mm dia(incl.specials)		1RM	
b	3.00	M	110 mm dia (incl.specials)		1RM	
c	1.00	RM	160 mm dia (incl.specials)		1RM	
55	6.00	M	Supplying and fixing of Supreme make SWR PVC Type-A pipes 110 mm dia including cutting charges, cost of cement solvent for joining and fixing with necessary SWR PVC plumbing specials for rain water line including necessary scaffolding etc., complete but excluding cost of specials and MS brackets which will be paid seperately.		1RM	
56	30.00	Kgs	Supplying and fixing of required size brackets and clamps using MS Angles, MS flats, and MS threaded rods as instructed by Engineer including one coat zinc chromate primer, two coats with synthetic enamel paint making holes in wall for fixing cement concrete for packing finishing the surfaces etc., complete		1Kg	
57			Supplying of G.I special clamp with coach screw, U bolt , nut & washer of the following sizes of G.I Pipe supports and specifications etc. complete.			
a	3.00	Nos	100 mm length		1No	
b	3.00	Nos	230 mm length		1No	
58			Supplying , cutting,threading, laying and joining of G.I. pipes ' B ' class ISI make with necessary ' UNIK' make specials including cost of all required materials, clamps, teak wood plugs and screws etc., complete. (ABOVE GROUND LEVEL)			
a	5.00	M	15mm dia		1RM	
b	5.00	M	20mm dia		1RM	
c	3.00	M	25mm dia		1RM	
d	3.00	M	32mm dia		1RM	
59	1.00	No	Supplying and fixing in position of White EWC with "S/P " trap parryware make including plastic seat cover white colour parryware with all required fittings etc., complete. (including 10 litre low level white P.V.C. flushing cistern)		1No	
60	1.00	No	Supplying and fixing in position of Parryware White glazed wash hand basin 550x400mm including all fittings such as 1" SS brackets, 15mm dia CP pillar cock (plumber make) 1st quality inlet nylon connection, CP waste coupling, etc., complete.		1No	
61	2.00	Nos	Supplying and fixing of Supreme make PVC nahini plain floor trap of 110mm dia. with S.S round jally including cost of cement solvent for joining, cement mortar for fixing in position etc., complete.		1No	
62	1.00	No	Supplying and fixing of 110mm dia Supreme make PVC multi floor trap with S.S. hinged type square of cement solvent for joining, cement mortar for fixing in position etc., complete.		1No	
63			Supplying and fixing in position of following types of bath room fittings of approved make including cost of all materials and required specials etc., complete.			
a	1.00	No	15mm dia CP long body bib cock		1No	
b	2.00	Nos	15mm dia CP Angle cock for WHB & flush tank.		1No	
c	1.00	No	15mm dia CP Two way bib cock with health faucet		1No	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
d	1.00	No	CP Bottle trap		1No	
e	1.00	No	15mm dia CP Open stop cock.		1No	
f	1.00	No	15mm dia CP short body bib cock		1No	
64	1.00	No	Supplying and Fixing in position of Chromium plated towel rod 600mm long with required teak wood plugs and screws including cost of all material etc., complete.		1No	
65	1.00	No	Supplying and fixing in position of mirror of size 600 x 450 mm with hard board back & plastic frame around including cost of all materials and required screws etc. complete.		1No	
66			Supplying and fixing in position of ISI Elco brand gun metal Gate valve heavy duty including cost of all materials and required specials etc., complete.			
a	1.00	No	25mm dia		1No	
b	1.00	No	32mm dia		1No	
c	1.00	No	40mm dia		1No	
67			Supplying and fixing of the following dia PVC pipes below ground level including cutting charges, cost of cement solvent for joining and fixing with necessary specials, earth work excavation, refilling, filling sand 150mm around pipe, refilling with excavated earth, cost of all materials etc., complete.			
a	5.00	M	75mm dia 6Kgs/CM ² (incl. specials)		1RM	
b	5.00	M	110mm dia 6Kgs/CM ² (incl. specials)		1RM	
68			Construction of Manhole chamber with 230mm thick brick wall using non metric bricks of size 230x115x75mm (chamber burnt) Plastering inside with CM 1:3, 20mm thick, Plastering outside with cm 1:5, 12mm thick upto 150mm below Finished Ground level, providing 50mm thick precast cover slab on top (But excluding cost of steel reinforcement) including earth work excavation, sand filling 75mm thick, CC 1:4:8 100mm thick, refilling the sides with excavated earth, finishing in all respects and curing etc. complete.			
a	1.00	No	Inner size-900 x 900 upto a depth of 1500mm		1No	
69	5.00	M ²	Painting two coats with Acrylic emulsion paint of approved make and colour over new walls and ceilings with one coat of water based primer after preparation of the surface smooth and even with Birla wall care putty/ approved equivalent including cost of all materials, proper roller finish, brush etc. complete.		1M ²	
70	5.00	M ²	Painting two coats with exterior acrylic emulsion paint of approved make and colour over new walls and ceiling with one coat of exterior water based primer incl, cleaning the surfaces, cost of all materials, brush and scaffolding etc complete.		1M ²	
71	5.00	M ²	Painting two coats with synthetic enamel paint of approved make colour over old / new walls with one coat of oil based primer after preparation of the surface smooth and even with Birla wall care putty / approved Equivalent including cost of all materials, coat of white cement base, brush and scaffolding etc. complete.		1M ²	
72			Painting new G.I. pipes with three coats consisting of one coat of zinc chromate primer and two coats of Ist quality synthetic enamel paint of approved make and colour incl. cleaning the pipes, cost of all materials and brush etc. complete.			
a	5.00	M	15mm dia		1RM	
b	5.00	M	20mm dia		1RM	
c	3.00	M	25mm dia		1RM	
d	3.00	M	32mm dia		1RM	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
73	5.00	M ²	Scraping completely and cleaning the white (or) colour washed surface (or) snowcem surface of old walls and ceilings using putty plate, sand paper and wire brush etc. incl. scaffolding and clearing the debris away from site etc. complete. (For Interior and Exterior surfaces).		1M ²	
74	1.00	M	Supplying and fixing of Aluminium angle 40x25x3mm in toilet area (or) other areas wherever the level difference in floor level etc,complete		1RM	
75			Making through holes in Plain or Reinforced Cement Concrete/Brickwork with Diamond Core Drilling System by using BOSCH power tools of following diameter			
a	3.00	Nos	upto 200mm (Plain or Reinforced Cement Concrete) thickness upto 250mm		1No	
b	3.00	Nos	upto 200mm (Brickwork) thickness upto 250mm		1No	
76	10.00	Nos	Drilling and fixing 20mm dia bolt,washer,net 200mm length and grouting with hilti chemical including the cost of material and fabrication charges etc., complete		1No	
77	2.00	M ²	Supplying and fixing in position of interlocking paving blocks M15 Grade 60mm thickness over well compacted sand cushion(sand filling shall be measured and paid for separately) including cost of all materials,well compacting with earth rammers,aligning, finishing in all respects etc., complete.The concrete slabs will be restrained on kerb walls/retaining walls,same will be measured and paid for separately.		1M ²	
78	5.00	M ²	Supplying and fixing in position of stainless steel pipe Hand rail using Top 50mm dia ,vertical 40mm dia, Horizontal 20mm dia - 3rows 16 gauge, 304 grade including cost of all materials, bending to required shape fixing, grouting with CM finishing in all respects etc. complete (For Ramp)		1M ²	
79	500.00	Kgs	Supplying, fabrication and erection of roof truss & purlin using of MS Pipe, S.H.S, Angle & Plate, 'B' class Apollo/equivalent charges including Cost of necessary tools & materials, labours, fabrication and welding Charges ,one coat primer & 2 coat of enamel paint as per instruction of engineer in charge, complete.		1Kg	
80	5.00	M ²	Providing and fixing precoated galvalume iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.		1M ²	
81	20.00	M ²	Supplying and fixing of roofing with sandwich roofing panel(PUF) 50mm thick external and internal steel wall facing in 0.5mm thick PPGI respectively of approved colour,insulation with rigid polyurethane foam density 40(+/-) 2Kg/M3, fixing the panels to the roof truss with perfect line and level without any damage and stains including cost of all materials, self tapping screws etc., complete as per manufacturer's specifications.		1M ²	

NAME OF THE WORK: MODIFICATION OF OLD SICU WAITING AREA TO PMR WAITING AREA @ CMC, TOWN CAMPUS.						
			TENDER SCHEDULE			
Sl.No.	Quantity		Description of the Work	Rate	Unit	Amount
82			Providing and fixing precast galvanized steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete.			
a	10.00	M	Internal Ridges plain (500 - 600mm).		1RM	
b	10.00	M	External Ridges plain (500 - 600mm).		1RM	
83	55.00	M	Supplying and fixing in position of plain Flashing sheet match with Roof profiled Sheet pre -painted galvanized steel sheet zinc coating 0.50mm thick of approved make and colour, with proper over laps, including cost of all materials, fixing with accessories, finishing in all respects etc., Complete.		1RM	
84			Supplying and fixing in position of following sizes of pvc rain water gutter 4Kgs/CM2 arrangements including cost of all materials, necessary supporting arrangements using 40x6mm M.S. flat which is to be bent to required shape and welded with truss ends & painting 2 coats of 1st quality of synthetic enamel paint over one coat of Zinc chromate primer, etc., complete			
a	10.00	M	160mm dia half round PVC pipe		1RM	
85	35.00	M ²	Labour charges for refixing the existing Aluminium Partition & Doors complete set without any damage including necessary modifications & all available fittings as directed.		1M ²	
86	2.00	No	Supplying and fixing in position of stainless steel pipe grab rail 25mm dia 18 gauge, 304 grade including cost of all materials, bending to required shape fixing, grouting with CM finishing in all respects etc. complete (total length 0.760m).		1No	
87	10.00	M	Supplying and fixing in position of 25mm dia (OD) MS powder coated curtain rod 20 gauge of approved make and colour including cutting cost of all materials etc., as directed by the engineer.		1RM	
88	4.00	Nos	Supplying and fixing in position of MS powder coated curtain brackets of approved make and colour with necessary wooden plugs/ supports and screws including cost of all materials etc., as directed by the engineer.		1No	
89	20.00	M ²	Providing & fixing "DAIKEN" gypsum ceiling tiles 9mm thick with Aluminium foil laminated on one side and PVC sheet laminated on the other side with hot dipped galvanized steel grid work, surface chemically cleaned capping PVC finished in backed polyester paint, main tees of size 33(H) x 24mm every 1.20m centre to centre, stiched cross tee at 0.60m centre to centre to form a grid of size 600x600mm & suspending the grid from roof using 3mm GI rod, 6mm nylon, rawl plug & I bolt at every 1200 intervals laying "DAIKEN" gypsum 155 ceiling tiles of size 600x600mm over the formed grid having fire rating of 60 minutes as per BS 479/23 of 1987, light reflection of 85%		1M ²	
90	1.00	No	Taking out C.I. cover with frame from R.C.C. top slab of manholes of various sizes including demolishing of R.C.C. work manually/ by mechanical means and stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead as per direction of Engineer-in-charge.		1No	
91	1.00	No	Supplying and fixing C.I. cover with frame for manholes 610x610 mm rectangular C.I. cover (Heavy duty) including cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete		1No	
92	11.00	Lorry loads	Transporting the debris by lorry from CMC Town campus to outside of the campus including loading and unloading charges etc. complete.(capacity- 5.50 M ³ /per lorry load).		1 Lorry load	
			Sub Total			
			ADD CGST-9%			
			ADD SGST-9%			
			Total			